


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Seward County. Sec. 9 Twp. 33S Rge. (E) 33 (W)  
Location as "NE/CNW/SW" or footage from lines SE NE  
Lease Owner Anadarko Production Company  
Lease Name Santa Fe Land Improvement Company "A" Well No. 2  
Office Address Box 351 Liberal, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 3-13 19 62  
Application for plugging filed 2-29 19 65  
Application for plugging approved 1- 3 19 66  
Plugging commenced 1-18 19 66  
Plugging completed 1-18 19 66  
Reason for abandonment of well or producing formation Non-economical

If a producing well is abandoned, date of last production 1- 4 19 66  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott Sublette, Kansas  
Producing formation Mississippian Depth to top 6024' Bottom 6037' Total Depth of Well 6125 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippian	Oil	6024'	6037'	8-5/8"	1568'	
				4-1/2"	6124'	2308'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mixed 20 sxs cement. Pumped plug to 5800' w/mud.  
Shot off 4-1/2" casing @ 2308'. Pulled casing to 700'.  
Pumped 35 sxs cement @ 700'. Finished pulling casing.  
Filled hole w/mud to 45'. Put 15 sxs cement from 45' to 0'.  
Complete @ 5:00 p.m. 1-18-66.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 31 1966

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sargent's Casing Pulling Service  
Address 1546 Clay Courts Liberal, Kansas

STATE OF Kansas, COUNTY OF Seward, ss.  
V. K. Downey (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. K. Downey, Supt. Liberal Production Division  
Box 351 Liberal, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of January, 1966  
Donald L. Vangerson  
Notary Public.

My commission expires Sept. 29, 1968


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company. ANADARKO PRODUCTION CO.  
Farm. Santa Fe Land No. 2  
Improvement Co. "A"

SEC. 9 T. 33 R. 33W  
C SE NE

Total Depth. 6126'  
Comm. 1-15-62 Comp. 2-9-62  
Shot or Treated.  
Contractor. Moran Bros.  
Issued. 6-30-62

County Seward  
KANSAS



CASING:  
8 5/8" 1568' cem w/850 sx.  
4 1/2" 6124' cem w/250 sx.

Elevation. 2788' GL

Production. 102 BOPD

Figures Indicate Bottom of Formations.

- sand 157
- sand & red beds 470
- sand & shells 714
- red bed, shells & sand 1075
- red bed & shells 1391
- sand, shale & Anhydrite 1570
- red bed, shale, shells w/shale 1981
- shale & shells 2321
- lime & shale 2838
- lime & shale 2894
- lime & shale 4559
- lime 4683
- lime, shale & chalk 4778
- lime & shale 6126
- Total Depth

RECEIVED  
CITY COMMISSIONER'S OFFICE

FEB 22 1966

- TOPS: SCOUT
- Council Grove 2898
- Toronto 4191
- Lansing 4311
- Marmaton 4970
- Morrow 5548
- Mississippi 5792
- St. Genevieve 6092

**OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING & FRACTURING INFORMATION**

Name	From	To	No. of Shots	Gallons Used	Kind Used
Mississippian	6024	6037		A/1,000	----
				F/15,000 + 10,000#	(Gelled Sand Acid Wtr.)