


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Seward County, Sec. 14 Twp. 33S Rge. 31W (E) (W)



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Panhandle Development Co., Inc.
Lease Name Stoddard Well No. 1
Office Address P. O. Box 1226, Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 11-30- 19 59
Application for plugging filed April 11 19 61
Application for plugging approved April 12 19 61
Plugging commenced April 12 19 61
Plugging completed 1:00 P.M. May 2, 19 61
Reason for abandonment of well or producing formation Quit producing

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
Producing formation Morrow Depth to top 5632 Bottom 5640 Total Depth of Well 6053 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Morrow</u>	<u>Oil & Gas</u>	<u>5632</u>	<u>5640</u>	<u>18"</u>	<u>30'</u>	<u>-----</u>
				<u>13 3/8"</u>	<u>518'</u>	<u>-----</u>
				<u>8 5/8"</u>	<u>2821</u>	<u>549.50'</u>
				<u>5 1/2"</u>	<u>5705</u>	<u>2828.92</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped 175 gallons gravel, hole bridged at 3318', dumped 5 sacks cement, top of plug at 3290', Ran free point and cut casing at 2816'. Pulled 1 joint 5 1/2" casing. Hydraulic pump broke down. Down for repairs 4-21-22, 23, 24, and 25. Start pulling casing 4-26-61. P lled 87 joints and piece 2828.92' overall. 4-30-61, ran free point on 8 5/8" casing to 550'. Cut off casing. Recovered 549.50' of 8 5/8", 24# casing. Put rock bridge back to 510'. Dumped 30 sacks cement. Filled with mud to 40', placed rock bridge and dumped 15 sacks cement. cut off Braden head and welded steel plate on top of 13 3/8" casing. Plugging completed 1:00 P.M. 5-2-61.

RECEIVED
STATE CORPORATION COMMISSION
MAY 12 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ray's Tubing & Casing Service
Address Liberal, Kansas

STATE OF Kansas, COUNTY OF Seward, ss.
H. J. Whitman (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. J. Whitman

(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of May, 19 61

Notary Public.

My commission expires September 16, 1964.


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- REPUBLIC NATURAL GAS COMPANY
Farm- Stoddard No. 1

SEC. 14 T. 33 R.31W
C SW SE

Total Depth. 5894'
Comm. 10-10-59 Comp. 10-28-59
Shot or Treated.
Contractor. Noble Drig. Corp.
Issued. 5-13-61

County Meade
KANSAS



CASING:
18" 30'
13 3/8" 518' cem w/600 sx.
8" 2821'
5 1/2" 5705' cem w/100 sx. Figures indicate Bottom of Formations.

Elevation. 2756' DF

Production. 10 BOPD

shale & sand	518
red bed, clay & gyp	1284
shale, red bed & anhy.	1842
shale, gyp & anhy.	2501
Anhydrite & lime	2823
lime	3855
lime & shells	3980
lime & shale	4405
lime	4694
lime & shale	4757
lime & shells	4846
lime	4901
lime & shale	5093
lime	5261
lime & shale	5773
lime	5820
lime & shale	5884
lime	5890
lime	5894
Total Depth	

TOPS:

Council Grove	3006
Toronto	4328
Lansing-Kansas City	4456
Marmaton	5086
Cherokee	5266
Morrow	5576
Lower Sand	5634
Chester	5647
Ste. Genevieve	5838

RECEIVED
STATE CORPORATION COMMISSION

FEB 22 1966

OBSERVATION DIVISION
Wichita, Kansas