

WELL PLUGGING RECORD

Information Completely Required Affidavit Deliver Report to: Conservation Division of Corporation Commission No. Market Wichita, Kansas

NORTH

Section plat grid with 'X' in the bottom-right cell.

Locate well correctly on above Section Plat

Seward County, Sec. 2 Twp. 33S Rge. 31W (E) (W) Location as "NE/CNW/SW" or footage from lines 660 FWL, 660 FSL, C-SW-SE Lease Owner: White Shield Oil & Gas Corp. Lease Name: Headrick "A" Well No. 2-1 Office Address: P. O. Box 2139, Tulsa, Okla. Character of Well: Oil Date well completed: 10-1 1970 Application for plugging filed: 2-8 1971 Application for plugging approved: 2-9 1971 Plugging commenced: 2-12 1971 Plugging completed: 2-17 1971 Reason for abandonment: Non-commercial If a producing well is abandoned, date of last production: Oct. 1970 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: N/A Producing formation: St. Louis Depth to top: 5929 Bottom: 5942 Total Depth of Well: 6040 Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: St. Louis, Oil, 5929, 5942, 8 5/8, 1609', 2464.08

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rigged up, mixed 20 sx of cement, displaced cement to 2800'. Filled hole w/mud. Mixed 35 sx of cement, displaced cement from 1000' to 900'. Rigged down, cleaned celler three feet deeper, put 10 sx of cement in top of 8 5/8 surface pipe. P & A 2-17-71

RECEIVED STATE CORPORATION COMMISSION MAR 9 1971 CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Bryon Jackson Address: Liberal, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss. J. D. VanHorn (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. D. VanHorn P. O. Box 2139, Tulsa, Okla. 74101 (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 1971

My commission expires January 18, 1973 Rosanne J. Miller Notary Public.