

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Finney State Office Building
 130 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-175-20,108-0001

LEASE NAME Traylor "A"

WELL NUMBER 2

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 2 TWP. 33S RGE 31 () or ()

COUNTY Seward

Date Well Completed 6/21/70

Plugging Commenced 5/4/95

Plugging Completed 5/16/95

TYPE OR PRINT
 NOTICE: **Fill out completely**
 and return to Cons. Div.
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/3/95 (date)

by Mr. Glenn Barlow (KCC District Agent's Name)

Is AC0-1 filed? Yes If not, is well log attached?

Producing Formation Morrow Depth to Top 5553 Bottom 5558 T.D. 6060

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Morrow	Gas	5553	5558	8-5/8"	1604'	3'
				4-1/2"	6059'	2697'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
TIH w/2-3/8 Tbg. to 5530, spot 30 sx class "H" cmt. TOH w/2-3/8 Tbg LD. MIRU csg pullers. Load hole w/fluid & run free pt. Shot csg. @ 2911, Loose @ 2730. Circ. hole w/ 9ppg mud. Spot 25 sx cmt from 2700-2600. Pull csg. to 1650 & spotted 50 sx cmt from 1650-1500. Pull csg. to 700 & spot 40 sx cmt. from 700-600. Pull csg to 33 & spot 10 sx cmt from 33 to 3'. Cut-off & capped 8-5/8 csg. 3' below G.L. RDMO csg pullers. REC 87 its. 4-1/2" csg. KCC witness: Glenn Barlow.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731 Phone: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

John M. Dolan, Sr. Technical Assistant (Employee of Operator) or (xxxxxxx) of above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) John M. Dolan

(Address) John M. Dolan, Sr. Technical Assistant
 P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 1st day of June, 1995

Freda L. Hinz
 Notary Republic

My Commission Expires:



STATE CORPORATION COMMISSION
 RECEIVED
 JUN 05 1995
 COMMUNICATIONS SECTION