


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Seward County, Sec. 4 Twp. 33-S Rge. (E) 31 (W)
Location as "NE/CNW%SW%" or footage from lines 3000' FSL-1972.74 FWL.
Lease Owner Cabot Carbon Company
Lease Name Nellie Burr Well No. 1
Office Address Box 1101, Pampa, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed August 14, 19 58
Application for plugging filed January 20, 19 60
Application for plugging approved January 21, 19 60
Plugging commenced February 11, 19 60
Plugging completed February 18, 19 60
Reason for abandonment of well or producing formation Failure to produce oil.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production December 7, 19 59
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W. L. Lac Kamp, Stafford, Kansas
Producing formation Marmaton Lime Depth to top 5031 Bottom 5041 Total Depth of Well 5990 Feet
Show depth and thickness of all water, oil and gas formations. Plugged back to 5076'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing-Kansas City	Salt Water	4662	4676	8-5/8"	2342'	none
Marmaton Lime	Oil	5031	5041	5-1/2"	5104'	3,822'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging commenced 2-11-60. Plugging completed 2-18-60. Measured into plug back at 5076'. Plugged off bottom with 100' of sand, 5076 to 4976'. Dumped 5 sacks of cement, 4976' to 4961'. Loaded hole with water. Worked and shot pipe. Shot 5 1/2" casing at 3822'. Pulled and layed down casing. Plugged hole with mud to 600'. Set 10' rock bridge at 600' to 590'. Dumped 20 sacks of cement on the rock, 590' to 530'. Mudded hole to 40'. Set 10' rock bridge, 40' to 30'. Capped the well with 10 sacks of cement, 30' to 0'.

RECEIVED
STATE CORPORATION COMMISSION
FEB 23 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company
Address Box 221, Great Bend, Kansas

STATE OF Texas, COUNTY OF Gray, ss.
O. B. Worley, Oil & Gas Accountant (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]*
Box 1101, Pampa, Texas (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of February, 19 60

[Signature] MARY K. JAYNES
Mary K. Jaynes Notary Public.

My commission expires June 1, 1961



