

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2125  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 175-21342-0001

LEASE NAME Massoni

WELL NUMBER 3-5

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1980 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 5 TWP. 33 RGE. 31 (N or W)

COUNTY Seward

Date Well Completed 12-15-93

Recompleted 12-19-94

Plugging Commenced 10-9-96

Plugging Completed 10-10-96

LEASE OPERATOR Cabot Oil & Gas Corporation

ADDRESS 9400 North Broadway, Suite 608

OKLAHOMA City, OK 73114

PHONE# (405) 478-6500 OPERATORS LICENSE NO. 6120

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-8-96 (date)

by Gary Winters (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Council Grove Depth to Top 3072' Bottom 3176' T.D. 3260'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				<u>8 5/8</u>	<u>1512</u>	<u>3176</u>
				<u>5 1/2</u>	<u>6100</u>	<u>2566</u>

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 31 1996  
CONSERVATION DIVISION  
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section.  
10-9-96 Mixed 1 SK hulls to 25 sx cmt. to plug perfs from 3072 to 2872.  
Shot 5 1/2 loose @ 2566. Pulled to 1540. Circ. hole w/mud to mixed 50 sx cmt.  
plug from 1540 to 1390. Pulled to 550 to mixed 50 sx plug from 550 to 400.  
Pulled to 40. Mixed 10 sx plug 40 to 0. Cut off & capped 8 5/8 3 ft. below G.L.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CABOT OIL & GAS CORPORATION

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

John P. Suter (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) John P. Suter

(Address) 9400 N. Broadway, Ste 608, OKC, OK 73114

SUBSCRIBED AND SWORN TO before me this 28th day of Oct, 19 96

Ornie B. Turner  
Notary Public

My Commission Expires: 9/21/2000

