


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Morton County, Sec. 5 Twp. 33S Rge. (E) 39 (W)
Location as "NE/CNW/SW" or footage from lines C-SE NW



Locate well correctly on above Section Plat

Lease Owner Anadarko Production Company
Lease Name Hayward "B" Well No. 1
Office Address Box 351 Liberal, Kansas 67901
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-6 19 69
Application for plugging filed Verbal approval 4-6 19 69
Application for plugging approved 4-6 19 69
Plugging commenced 4-6 19 69
Plugging completed 4-6 19 69
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves Sublette, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 6514 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1673'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Spotted 45 sacks of cement from 1600' - 1700'.
Spotted 35 sacks of cement from 800' - 900'.
Spotted 15 sacks of cement from 45' - 0'.
Completed @ 5:00 p.m. 4-6-69.


RECEIVED
STATE CORPORATION COMMISSION
APR 15 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Lohmann-Johnson Drilling Company
Address Oklahoma City, Oklahoma

STATE OF Kansas, COUNTY OF Seward, ss.
V. K. Downey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

V. K. Downey (Signature) [Signature]
Superintendent P.O. Box 351 Liberal, Kansas 67901
Liberal Production Region (Address)

Subscribed AND SWORN TO before me this 11 day of April, 1969
[Signature]
Notary Public.



My Commission Expires April 28, 1971.

15-129-20036-00-00

DRILLER'S LOG

WELL NAME: Hayward "B" No. 1 ; COMPANY OPERATING: Anadarko Production Company
 ADDRESS of COMPANY: Box 351 Liberal, Kansas 67901

WELL LOCATION: C 1/4 SE 1/4 NW 1/4,
3300 ft. North of South line,
1980 ft. East of West line: Sec. 5, Twp. 33S, Rge. 39W, Morton County, Kansas

DRILLING STARTED 3-23, 1969; DRILLING COMPLETED 4-6, 1969
 WELL COMPLETED _____, 19____; WELL CONNECTED _____, 19____

ELEVATION: 3242.95 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Dry Hole

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used

RECEIVED
 STATE CORPORATION COMMISSION
 APR 15 1969
 CONSERVATION DIVISION
 Wichita, Kansas

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8"	1673'	800	None

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Sand and Shale	0'	695'	Shale & Sand	5820'	6069'
Red Bed Shale & Sand	695'	1625'	Lime	6069'	6514'
Red Bed & Shale	1625'	1661'	Total Depth	6514'	
Anhydrite	1661'	1674'			
Shale	1674'	2376'			
Shale & Lime	2376'	2810'			
Lime	2810'	4235'			
Lime & Shale	4235'	5020'			
Lime	5020'	5084'			
Shale	5084'	5185'			
Shale & Lime	5185'	5455'			
Shale	5455'	5620'			
Lime & Shale	5620'	5820'			

RESULTS of INITIAL PRODUCTION TEST: P & A 4-6-69