

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Finney State Office Building
 130 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-189-21,243-00-03

LEASE NAME TEXACO "A"

WELL NUMBER 1

1250 Ft. from S Section Line

1250 Ft. from W Section Line

SEC. 15 TWP. 33S RGE 39 (E) or (W)

COUNTY STEVENS

Date Well Completed 09/23/88

Plugging Commenced 04/20/97

Plugging Completed 04/21/97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 04/07/97 (date)

by MR. GARY WINTERS (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation MARMATON Depth to Top 4848' Bottom 4862' T.D. 6550'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
MARMATON	GAS	4848'	2700'	8-5/8"	1690'	985'
KEYES	GAS	6104'	6108'	4-1/2"	6264'	3'
MORROW	GAS	5976'	6060'			

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. MIRU PU, PMPD 20 SXS CMT TO PLG 4592-4862, PULLED FREE PT, SHOT OFF CSG @ 1095, PIPE STUCK, SHOT OFF @ 985, PULLED TO 800', PMPD 90 SXS CMT PLG FROM 500-800, PULLED TO 40, PMPD 10 SXS CMT PLG FROM 0-40, CUT OFF, & CAP 4-1/2 CSG 3' BELOW GL. INSCRIBE CAP. RDMO. RESTORE LOCATION. KCC REP GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 15th day of July, 1997

Shirley J Childers
 Notary Public

My Commission Expires: _____

