

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Morton SEC. 5 TWP. 33S RGE. 39 E/W
 Location as in quarters or footage from lines:
1250' FS. & WL

		5	

Lease Owner Anadarko Production Company
 Lease Name SCHMIDT "B" Well No. 1
 Office Address P. O. Box 351, Liberal, Kansas 67901
 Character of Well (Completed as Oil, Gas or Dry Hole): DRY HOLE
 Date Well Completed March 3, 1982
 Application for plugging filed December 20, 1981
 Plugging commenced March 3, 1982
 Plugging completed March 3, 1982
 Reason for abandonment of well or producing formation DRY HOLE

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
 Producing formation _____ Depth to top _____ bottom _____ T.D. 6147
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8	1667	-0-
				4-1/2	6142	3616'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Mixed 20 sxs cmt, pmpd plug 5700' w/hvy mud, shot off 4-1/2" csg 2616, st pulling casing,
spotted 25 sxs cmt 2600-2500, 50 sxs cmt 1650-1550, 25 sxs cmt 620-520, comp pulling csg,
filled hole w/hvy mud, formed bridge 40', spotted 10 sxs cmt 40-0.

RECEIVED
 STATE CORPORATION COMMISSION
 APR 5 1982
 TRANSEIVA, JULY 1982
 WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Sargents Casing Pulling Service

STATE OF KANSAS COUNTY OF SEWARD, ss.
Paul Campbell (employee of owner) or (~~owner or operator~~) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Paul Campbell
P. O. Box 351, Liberal, Kansas 67901
 (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of April, 19 82

STATE NOTARY PUBLIC
 BEVERLY J. WILLIAMS
 Seward County, Kansas
 My Appt. Exp. November 21, 1982

Beverly J. Williams
 Notary Public.

My Commission expires November 21, 1982

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Schmidt "B" #1
1250' FW & SL Sec 9-33S-39W
Morton County Kansas

Commenced: 10-31-81

Completed: 11-12-81

OPERATOR: ANADARKO PRODUCTION CO.

Depth		Formation	Remarks
From	To		
0	121	Grass Roots-Sand	
121	1190	Sand-Redbed	Ran 39 jts of 24# 8 5/8" csg set @ 1670' Cemented w/
1190	1442	Anhy-Sand-Redbed	550 sks Posmix 4% Gel 2% CC
1442	1672	Redbed-Sand	+ 250 sks Common 2% CC
1672	2033	Anhy-Lime-Shale	PD @ 12:00 Midnight 11-1-81
2033	6120	Lime-Shale	
	6120 - TD		Ran 145 jts of 11.6# 5 1/2" csg set @ 6142' Cemented w/50 sks Lite - 150 sks 50/50 Posmix Salt Sat PD @ 8:00 p.m. 11-12-81

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 23rd day of November, 1981.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

ELIZABETH J. EDWARDS
NOTARY PUBLIC
NOV 23 1981

RECEIVED
STATE CORPORATION COMMISSION

NOV 24 1981

CONSERVATION DIVISION
Wichita, Kansas