

15-175-20662-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
Form CP-4
Rev. 12-15-80
DEC 16 1982
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Seward SEC. 24 TWP. 33S RGE. 33W E/W
Location as in quarters or footage from lines:
SW SW $\frac{1}{4}$

Lease Owner Kennedy & Mitchell, Inc.
Lease Name Hunt Well No. 50-947
Office Address P.O. Box 1869, Liberal, KS 67901
Character of Well (Completed as Oil, Gas or Dry Hole): Dry, abandoned
Date Well Completed N/A
Application for plugging filed 12-6-82
Plugging commenced 12-11-82
Plugging completed 12-11-82
Reason for abandonment of well or producing formation Dry hole

Locate Well
correctly on above
Section Plat.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.
Producing formation St. Louis Depth to top _____ bottom _____ T.D. 6300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	1511'	none

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____
feet to _____ feet for each plug set. 1st plug, 70 sx 50/50 POZ, 4% gel, 3% cc @ 1800'
2nd plug, 40 sx, 50/50 POZ, 4% gel, 3% cc @ 450' - Top plug, 10 sx 50/50 POZ,
4% gel, 3% cc @ 40'-0' - 10 sx in rathole & 10 sx in mousehole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton, Liberal, KS


STATE OF Kansas COUNTY OF Seward, ss.
R.F. Burke (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R.F. Burke
P.O. Box 1869, Liberal, KS 67901
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of December, 19 82

Denise Geist
Notary Public.

My Commission expires: 2-26-83



DRILLERS LOG

HUNT NO. 50-947

CASING RECORD: OPERATOR: Kennedy & Mitchell, Inc. DESCRIPTION:
 8-5/8" set @ 1511' CONTRACTOR: Sage Drilling Co., Inc. SW SW
 w/800 sax cement Section 24-33S-33W
 Seward County,
 Kansas
 TOTAL DEPTH: COMMENCED: November 22, 1982
 6300' COMPLETED: December 5, 1982

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Red Bed	0	1010	
Sand, Red Bed & Anhydrite	1010	1487	
Red Bed	1487	2475	
Lime & Shale	2475	2598	
Dolomite	2598	2865	
Lime, Shale & Dolomite	2865	3070	
Shale & Lime	3070	3335	
Dolomite	3335	3540	
Lime & Shale	3540	3760	
Shale & Lime	3760	3970	
Lime & Shale	3970	4360	
Shale & Lime	4360	4450	
Lime & Shale	4450	4785	
Shale & Lime	4785	4920	
Lime & Shale	4920	5410	
Shale & Lime	5410	5503	
Lime	5503	5590	
Lime & Shale	5590	5700	
Shale & Lime	5700	5745	
Lime & Shale	5745	5920	
Shale & Lime	5920	6020	
Lime & Shale	6020	6269	
Lime	6269	6300	

STATE RECEIVED
 JAN 26 1983
 Notary Public
 Wichita, Kansas

Ran DST #1-4
 Logged Hole,
 D & A

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.

SAGE DRILLING CO., INC.

BY John R. Bartholomew
 John R. Bartholomew

Subscribed and sworn to before me this 23rd day of December, 1982.

Nancy J. Bertram
 Nancy J. Bertram, Notary Public

