

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2125
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20,978-00-00

LEASE NAME Boyer Trust

WELL NUMBER 1-24

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4270 Ft. from S Section Line

3280 Ft. from E Section Line

LEASE OPERATOR Harris Oil & Gas

SEC. 24 TWP. 33 RGE. 33 (N or W)

ADDRESS 1125 17th Street, Ste 2290 Denver, CO 80202

COUNTY Seward

PHONE# (303) 293-8838 OPERATORS LICENSE NO. 9963

Date Well Completed 7-12-88

Character of Well GAS

Plugging Commenced 2-17-97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-20-97

The plugging proposal was approved on 2-18-97 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Wichita, Shallow Depth to Top 5824; 6216 Bottom 5845; 6220 T.D. 6300

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS RECEIVED
KANSAS CORPORATION COMMISSION CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	MAY 06 1997			8 5/8	1633	
				4 1/2	5975	2632
				3 1/2	5751 to 6300	
	CONSERVATION DIVISION WICHITA, KS					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s
2-18 Mixed 2 sx hulls & 20 sx cmt. to plug perfs from 6216 to 6016. Shot 4 1/2 loose @ 2632. 2-19 30 sx plug 2600 to 2500. 50 sx plug 1660 to 1510. 40 sx plug from 550 to 450. 10 sx plug 40 to 0. 2-20 cut off & cap 8 3/8 4 ft. below ground level.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: HARRIS Oil & Gas Company

STATE OF KANSAS COUNTY OF SEWARD, ss.

HAROLD FRAULI, AGENT (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fac statements, and matters herein contained and the log of the above-described well as filed; the same are true and correct, so help me God.

(Signature) Harold K Frauli

(Address) _____

RECEIVED
KCC DISTRICT #2

MAY 05 1997

SUBSCRIBED AND SWORN TO before me this 29th day of APRIL, 19 97

Helen C. Berg

NOTARY PUBLIC
State of Kansas Notary Public
HELEN C. BERG
My Appt. Exp. 9-18-99

WICHITA, KS My Commission Expires: _____