

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20,913-0000

LEASE NAME BUSH "C"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 25 TWP. 33S RGE. 33 (E) or (W)

COUNTY Seward

Date Well Completed 9/25/86

Plugging Commenced 9/26/86

Plugging Completed 9/26/86

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation none Depth to Top _____ Bottom T.D. 6430

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surf	1587	8-5/8"	1587'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped 50 sacks cement from 1590-1386', 25 sacks cement from 660-558', 10 sacks cement from 40-0' and 10 sacks cement in rathole and mousehole. Heavy drilling mud was spotted between each plug. Complete 3:00 hrs 9/26/86.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. _____


Address P. O. Box 1598, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.

M. L. Pease, Division Production Engineer (Employee of Operator) or ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

(Address) P. O. Box 351, Liberal, KS 67901



TO before me this 22nd day of October, 19 86

Beverly J. Williams
Notary Public

My Commission Expires: November 21, 1986