

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Seward SEC. 26 TWP. 33S RGE. 33 XE/W
 Location as in quarters or footage from lines:
C NE SW

		25	

Lease Owner Anadarko Production Company
 Lease Name SALLEY "B" Well No. 1
 Office Address P. O. Box 351, Liberal, Kansas 67901
 Character of Well (Completed as Oil, Gas or Dry Hole): Gas
 Date Well Completed July 5, 1967
 Application for plugging filed November 12, 1982
 Plugging commenced January 8, 1983
 Plugging completed January 10, 1983
 Reason for abandonment of well or producing formation Depleted

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation Morrow Depth to top 5812' bottom 5879' T.D. 6270'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Morrow</u>	<u>Gas</u>	<u>5812</u>	<u>5879</u>	<u>8-5/8"</u>	<u>1584'</u>	<u>0</u>
				<u>4-1/2"</u>	<u>6270'</u>	<u>2700'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spot 1 sx hulls and 25 sxs cmt @ 5600', shot casing at 5191, 3026 and 2700. Casing free @ 2700, pulled 84 jts 4-1/2" casing. Spot 50 sxs cmt @ 2350, 50 sxs cmt @ 1700, 25 sxs @ 600 and 10 sxs cmt 40-0. Cut off 8-5/8" casing and cap well.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Sargents Casing Pulling Service

STATE OF Kansas COUNTY OF Seward, ss.

Paul Campbell (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul Campbell
P. O. Box 351, Liberal, Kansas 67901
 (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of January, 19 83



Beverly J. Williams
 Notary Public.

My Commission expires November 21, 1986

JAN 27 1983

