

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
130 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-175-21416-0000

LEASE NAME GAREY 'A'

WELL NUMBER 2

1420 Ft. from S Section Line

3860 Ft. from E Section Line

SEC. 27 TWP. 33 RGE 33 ( E ) or ( W )

COUNTY SEWARD

Date Well Completed 12-12-94

Plugging Commenced 8-2-95

Plugging Completed 8-7-95

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well DRY

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-1-95 (date)

by GLENN BARLOW (KCC District Agent's Name).

Is AC0-1 filed? YES (2-06-95) If not, is well log attached? \_\_\_\_\_

Producing Formation NONE Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 2688

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				13-3/8"	655'	NONE
				8-5/8"	2600'	1210'
				5-1/2"	2688'	NONE

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

MIRU PLUGGERS. PMPD 4SXS HULLS & 30 SXS CMT PLG FROM 2553-2453' PULL FREE POINT. SHOT 8-5/8" @ 1593'. PMPD 50 SXS CMT PLG FROM 1593-1493'. TOH TO 1393'. SD FOR W/E. PIPE STUCK. SHOT @ 1140', COULD NOT PULL. SHOT @ 1010. PULL TO 700'. PMPD 80 SXS CMT PLG FROM 700-600'. TOH W/CSG. PMPD 30 SXS CMT PLG FROM 33-3'. CUT OFF 13-3/8" & CAP. RDMO PLUGGERS. KCC WITNESS: GLENN BARLOW.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGERS, INC. License No. 31151

Address RT 1. BOX 49BA, TYRONE, OKLAHOMA 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

DAVID W. KAPPLE (Employee of Operator) or (xxxxxxx) of above described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David Kapple

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 16th day of August, 19 95

My Commission Expires:



L. Marc Harvey  
Notary Public