

15-175-00156-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
100 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER June 4, 1954

LEASE NAME GAREY

WELL NUMBER 1-27

2757 Ft. from S Section Line

2809 Ft. from E Section Line

SEC. 27 TWP. 33S RGE. 33 ~~06W~~ (W)

COUNTY Seward

Date Well Completed 6-22-54

Plugging Commenced 5-8-90

Plugging Completed 5-8-90

TYPE OR PRINT
NOTICE: Fill out **completely**
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR APX CORPORATION

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 5598

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-27-90 (date)

by Shari Feist Albrecht (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached? _____

Producing Formation Chase Depth to Top 2604 Bottom 2708 T.D. 2708

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surface	566	10 3/4	566	0
			2708	7	2604	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. TOH w/tbg & rods, TIH w/2 3/8 tbg. Cmt w/Class "H" as follows: 50 sxs cmt plg @ 2700', 40 sxs cmt plg @ 1580', 40 sxs cmt plg @ 600', 10 sxs cmt plg @ 40'-0'. Heavy DM pmpd between each plg. Cut off 3' below ground level and cap well. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506, Liberal, Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: APX CORPORATION

STATE OF Kansas COUNTY OF Seward, ss.

M. L Pease, Division Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L Pease

(Address) M. L Pease, Division Production Mgr. P.O. Box 351, Liberal, KS 67905-0351

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1990
CONSERVATION DIVISION
WICHITA, KANSAS

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 19 90

My Commission Expires: _____

CHERYL STEERS
Notary Public - State of Kansas
My Appt. Expires 6-1-93

(Cheryl Steers)
Notary Public