

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
30 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 1517521042 -00-01

LEASE NAME PRIEFFERT

WELL NUMBER C-1H

1980 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 34 TWP. 33S RGE 33 ( E ) or ( W )

COUNTY SEWARD

Date Well Completed 11-30-89

Plugging Commenced 12-18-2002

Plugging Completed 12-20-2002

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

PHONE # ( 806 ) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-10-2002 (date)

by JIM HOLLAND (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation CHASE Depth to Top 2612 Bottom 2705 T.D. 6250

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHASE	GAS	2612	2705	8 5/8"	1564	0
				4 1/2"	3160	0

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. SET CIBP AT 2550. DUMP 2 SXS CMT ON PLUG WITH BAILER. PRESSURE TO 500#. PERF 1000-1001 W/ 4 SPF. PUMP 350 SXS CMT CIRCULATED TO SURFACE. CUT OFF AND CAP 8 5/8" 4 BELOW GL. RDMO.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ALLIED CEMENTING License No. \_\_\_\_\_

Address PO BOX 31 RUSSELL, KS 67665 PHONE: (785) 483-2627

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.  
CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Craig R. Walters  
CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101

SUBSCRIBED AND SWORN TO before me this 6 day of March, 2003

Lori Pearson  
Notary Public

My Commission Expires: 2/26/05



Form CP-4  
Revised 05-88

RECEIVED  
MAR 10 2003  
KCC WICHITA