

15-119-10033-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

Well was completed on  
API NUMBER 12-7-52

LEASE NAME Novinger Unit

WELL NUMBER 801W

3300 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 35 TWP. 33S RGE. 30 (~~E~~W)

COUNTY Meade

Date Well Completed 12-7-52

Plugging Commenced 4-18-88

Plugging Completed 4-22-88

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS 3545 N.W. 58th Street, Oklahoma City, OK 73112

PHONE#(405) 949-4268 OPERATORS LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 14, 1988 (date)

by District 11 (KCC District Agent's Name).

Well was completed on:  
Is ACO-1 filed? 12-7-52 If not, is well log attached? Yes

Producing Formation Marmaton Depth to Top 5326 Bottom 5343 T.D. 5950

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Marmaton	Oil	5326	5343	13-3/8	645'	
				9-5/8	2708'	2742
				5-1/2	5850'	505

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set CIBP at 5000' & dumped 2 sx C1 H cmt. on top. Cut off csg. at 3212' & 2728'. Csg. came loose. Circ. w/45 bbls. 9.0 ppg drilling mud. Spotted 50 sx C1 H cmt. from 2615-2715'. Cut off 9-5/8" csg. at 1212', 1014', 1715' and 511'. Csg. came loose. Loaded csg. w/10 bbls. 9.0 ppg drilling mud. Circ. w/additional 10 bbls. of 9.0 ppg mud. Spotted 50 sx. C1 H (If additional description is necessary, use BACK of this form.) (over)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506 Liberal, Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bryan Humphries

(Address) 3545 N.W. 58th Street, Oklahoma City, OK 73112

SUBSCRIBED AND SWORN TO before me this 9th day of June, 19 88

Marsha B. Williams  
Notary Public

My Commission Expires: 4-1-92

PLUGGING PROCEDURES CONTINUED:

cmt. from 411-511'. Loaded hole w/10 bbls 9.0 ppg drilling mud to 40'. Spotted  
20 sx C1 H cmt. from 40' to surface. Cut off 13-3/8" csg. to 3' BGL. P&A completed.