

15-119-00046-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

MEADE County, Sec. 36 Twp. 33 Rge. 30W (E) (W)

Location as "NE/CNW*SW*" or footage from lines NE SW
Lease Owner R. W. LANGE
Lease Name FOX Well No. 2
Office Address P. O. BOX 1034 - GARDEN CITY, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) GAS
Date well completed 19__
Application for plugging filed SEPTEMBER 25 19 65
Application for plugging approved 19__
Plugging commenced SEPTEMBER 28 19 65
Plugging completed OCTOBER 7 19 65
Reason for abandonment of well or producing formation DEPLETED

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. HUGH SCOTT
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5879' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1472'	NONE
				5 1/2"	5790'	3191.41'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

5879'	-	5688'	-	PUMPED 25 SACKS CEMENT
5688'	-	700'	-	MUD
700'	-	600'	-	PUMPED 35 SACKS CEMENT
600'	-	35'	-	MUD
35'	-	BASE	-	PUMPED 15 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION

NOV 1 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address P. O. BOX 562 - GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
T. L. NUTT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt
P. O. BOX 562 - GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of October 19 65

Mary M. Guesnier
Notary Public.

My commission expires JULY 31, 1966

OWNER JAMES DONOGHUE

TRK. 30 T. 33S R. 30W

FARM FOX

NO. 2

LOC. C/NE, SW


TOTAL DEPTH 5879'

COUNTY Meade Co., Kansas

COMM. January 30, 1957

COMP. February 25, 1957

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 1472' W/850 sax.
5 1/2" @ 5790' W/100 sax.

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

100	Clay
250	Sand & clay
655	Sand & shale
730	Red bed & sand
900	Red rock, sand & gyp
1250	Sand & shale
2350	Shale & shells
3114	Lime & shale
3122	Lime
3520	Lime & shale
3610	Chalky lime & shale
4613	Lime & shale
5052	Lime
5167	Lime & shale
5274	Lime
5338	Lime & shale
5446	Lime
5547	Lime & shale
5660	Lime
5700	Lime & shale
5758	Lime
5782	Lime & shale
5815	Lime, shale & sand
5838	Sand & shale
5879	Lime & shale
5879	T. D.

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1965
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON } ss:

I, Verne A. Morris of Garvey Drilling Co.

upon oath state that the above and foregoing is a true and correct copy of the log of the #2 Fox well

Verne A. Morris

Subscribed and sworn to before me this 4th day of March 19 57

My Commission Expires: November 12, 1958

[Signature]
NOTARY PUBLIC