

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-175-10088-00-00

API NUMBER NA SPUD 5-23-63

LEASE NAME GAREY

WELL NUMBER 2-27

2777 Ft. from S Section Line

2789 Ft. from E Section Line

SEC. 27 TWP. 33S RGE. 33 (E) or (W)

COUNTY SEWARD

Date Well Completed 6-7-63

Plugging Commenced 5-12-98

Plugging Completed 5-13-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-4-98 (date)

by GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached?

Producing Formation GLORIETTA Depth to Top 1084 Bottom 1210 T.D. 1250

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
GLORIETTA	WATER	1084	1210	2-7/8"	1250	0

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU SARGENT & HORTON. TIH W/ 1-1/2" TBG TO 1210. PMP 25 SXS CMT TO PLUG 1210-300. POH TO 300. PMP 5 SXS CMT TO PLUG 300 TO 0'. POH W/ 1-1/2" TBG. CUT OFF AND CAP 2-7/8" TBG 4' BELOW GL. RDMO SARGENT & HORTON. WITNESSED BY STATE REP. GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Shawn D. Young
SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 25th day of September, 1998.

Shirley J. Childers
Notary Public

My Commission Expires:

