

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Seward County. Sec. 15 Twp. 33 S Rge. (E) 31 (W)

Location as "NE/CNW/SW" or footage from lines C SW NE

Lease Owner J. M. Huber Corporation

Lease Name RINEHART Well No. 1

Office Address P. O. Box 831, Borger, Texas 79007

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed 7-28-62 19

Application for plugging filed 5-9-73 19

Application for plugging approved 5-11-73 19


Plugging commenced 7-20-73 19

Plugging completed 7-24-73 19

Reason for abandonment of well or producing formation Uneconomical

If a producing well is abandoned, date of last production October 19 72

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. E. Eves

Producing formation Morrow/Marmaton Depth to top 5060 Bottom 5619 Total Depth of Well 5654 Feet

Show depth and thickness of all water, oil and gas formations. PBTB

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand & Shells	Water	0	680	8 5/8"	2250	0
Red Bed, Anhydrite & Shale	--	680	2137	5 1/2"	5730	2633
Lime & Shale	680	2137	3045			
Lime	Gas & SW	3045	3350			
Lime & Shale	--	3350	5000			
Lime	Gas & SW	5000	5100			
Lime & Shale	--	5100	5600			
Sand	Gas & SW	5600	5654			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Spotted 25 sacks cement thru tubing 5169-4950'. Shot off 5 1/2" casing @ 2622'.  
Loaded hole w/mud. Pulled casing to 900'  
Spotted 35 sacks cement 900-800'. POH. Spotted 15 sacks cement 40-5'.  
Recovered 2633' 5 1/2" casing

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 2 1973  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sargents Casing Pulling Service  
Address 620 So. Lincoln, Liberal, Kansas 67901

STATE OF TEXAS, COUNTY OF HUTCHINSON, ss.  
John L. Dannelley (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John L. Dannelley  
P. O. Box 831, Borger, Texas 79007  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of July, 19 73

My commission expires 6-1-75

Meryle M. Chambliss  
Notary Public  
In & for Hutchinson County, Texas

15-175-10045-0000  
- well file

J. M. Huber Corporation

Rinehart # 1

Section 15-33s-31w

Seward County, Kansas

Casing Record:

Commenced: 5-2-62  
Completed: 6-5-62

Ran 82 jts, 8-5/8" OD Casing, set : 2550'  
G.L., stage collar set @ 882', cemented  
bottom stage w/550 sacks Pozmix 2% gel,  
followed w/100 sacks Pozmix 2% cc, cemented  
w/560 sacks Pozmix 2% cc.  
Ran 179 jts, 5732.5, 5 1/2" OD casing, set at  
5730' KB, cemented w/215 sacks Pozmix.

Formation:

	<u>From</u>	<u>To</u>
Sand & Shells	0	535
Sand	535	680
Red Bed and Gyp	680	1050
Red Bed, Sand & Anhydrite	1050	1565
Red Bed, & Anhydrite	1565	2027
Red Bed, Anhydrite & Shale Streaks	2027	2137
Shale and Lime	2137	2336
Lime	2336	2374
Lime and Shale	2374	2468
Lime	2468	2514
Lime and Shale	2514	2551
Lime	2551	2625
Lime and Shale	2625	3311
Lime	3311	3435
Lime and Shale	3435	4080
Lime	4080	4246
Lime and Shale	4246	4427
Lime	4427	4684
Lime and Shale	4684	4740
Lime	4740	5222
Lime and Shale	5222	5271
Lime	5271	5344
Lime and Shale	5344	5584
Lime and Sand	5584	5625
Lime	5625	6010

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 11 1973  
CONSERVATION DIVISION  
Wichita, Kansas


RTD

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEWARD )

I Hereby affirm that the above and foregoing is a true and correct copy of the log of the Rinehart #1 well, located in Section 15.33s.31w, Seward County, Kansas.

McCLELLAN DRILLING INC

*[Signature]*  
C. J. McClellan



Subscribed and sworn to before me a notary public this 8<sup>th</sup> day of June, 1962.

*[Signature]*  
Sharon K. Halbrook, Notary Public

My Commission expires September 26, 1965.