

15-175-10087-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME Wheatly

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 23 TWP. 33 RGE. 31W R&W (W)

COUNTY Seward

Date Well Completed 1-16-61

Plugging Commenced 7-28-92

Plugging Completed 7-31-92

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A.L. Abercrombie

ADDRESS RT #1 Box 56 Great Bend, Kansas 67530

PHONE# (316) 793-8186 OPERATORS LICENSE NO. 5393

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Glen Barlow (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 6025'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	1235'	none
				5 1/2"	6014'	2272'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom to 4235', ran 5 sacks cement. Shot pipe @3000', 2700', 2500', 2272'. Plugged with 300# hulls, 15 gel, 50 sacks cement, 10 gel, 100# hulls, 8 5/8" wiper plug 175 sacks cement on top.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A.L. Abercrombie

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Handwritten Signature]

(Address) P.O. Box 347 Chase,

SUBSCRIBED AND SWORN TO before me this 5 day of August AUG, 19 92

[Handwritten Signature]
Notary Public

My Commission Expires:



Form CP-4
Revised 05-88

WHEATLEY #2
Panhandle Development Co., Inc.
Section 23-33S-31W
Seward County, Kansas

COPY

CASING RECORD:

Ran 60 joints of new 25.5# 8 5/8" casing, set at 1235.49 K.B., cemented with 450 sacks light water 2% C.C. 200 sacks common 2% C.C., ran 122 joints 5 1/2" 3000# test casing, set at 6014', cemented with 125 sacks on bottom stage and 100 sacks on top stage.

Commenced: 12-20-61
Completed: 1-16-62

FORMATION

FORMATION	FROM	TO
Top Soil	0	225
Sand	225	580
Red Bed and Gypsm	580	925
Red Bed and Sand	925	1252
Red Bed and Anhydrite	1252	2280
Anhydrite and Shale	2280	2430
Lime and Shale	2430	4430
Lime	4430	4807
Lime and Shale	4807	4965
Lime	4965	5291
Lime and Shale	5291	5335
Lime	5335	5471
Lime and Shale	5471	5639
Lime	5639	6025 RTD

State of Kansas)
) SS
County of Sedgwick)

I Hereby affirm that the above and foregoing is a true and correct copy of the log of the Wheatley #2 well, located C-NE-SW of Section 23-33S-31W, Seward County, Kansas.

PANHANDLE DEVELOPMENT CO., INC.

B. Lynn Henington
Accountant

Subscribed and sworn to before me a notary public this 20 day of June, 1962.

Leah Jaye Hofer
Notary Public

My Commission Expires June 16, 1963.

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1962
CONSERVATION DIVISION
Wichita, Kansas