

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colprado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-175-10084-0001

API NUMBER NA

LEASE NAME Wheatly SWD

WELL NUMBER 1

660 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 23 TWP. 33 RGE. 31 (X) or (W)

COUNTY Seward

Date Well Completed 6-1-60

Plugging Commenced 7-31-92

Plugging Completed 8-3-92

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS Rt. #1, Box 56 Great Bend, Ks. 67530

PHONE# (316) 793-8186 OPERATORS LICENSE NO. 5393

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 19, 1992 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filled? \_\_\_\_\_ If not, Is well log attached? Yes

Sand  
Producing Formation Gloretta Sand Depth to Top 1006 Bottom 1100 T.D. 6000

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1387	None
Gloretta Sand	Sand	1006	1100	5 1/2	1029	None
				3 1/2	1003	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
7-31-92 Pump Total 400# Hulls - 75 sacks 60/40 Poz displace down tubing to 700', shut in.  
8-3-92 Total Depth 700' Perf 4 shots 650-651; 500-501; & 424-425. Pump 125 sacks 60/40 Poz down tubing. Pump 10 sacks cement down 8 5/8 x 5 1/2 annulus Shut in 500# standing.

(If additional description is necessary, use BACK of this form.)

Name of State Pluggger Glenn Barlow

Name of Plugging Contractor A. L. Abercrombie, Inc. License No. 5393

Address Rt. #1, Box 56 Great Bend, Kansas 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A. L. Abercrombie, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

E. L. Abercrombie (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) E L Abercrombie

(Address) Rt. #1, Box 56 Great Bend, Kansas



SUBSCRIBED AND SWORN TO before me this 5th day of August AUG 7 1992

Susan M. Evers  
Notary Public  
Wichita, Kansas

My Commission Expires: 7-29-96

WHEATLEY #1  
Panhandle Development Co., Inc.  
Section 23-33S-31W  
Seward County, Kansas

COPY

CASING RECORD:

Run 71 joints of 8 5/8" used casing, set at 1387.53 K.B., cemented with 300 sacks of common, run 191 joints of 5 1/2" 8rd R 1 & 2 3000# test used 15.5# casing, set at 5997'.

Commenced: 5-7-60  
Completed: 6-1-60

FORMATION

	FROM	TO
Sand	0	580
Red Bed and Sand	580	1435
Red Bed and Anhydrite	1435	2460
Lime and Shale	2460	5772
Lime	5772	6000 RTD

State of Kansas )  
                          ) SS  
County of Sedgwick)

I Hereby affirm that the above and foregoing is a true and correct copy of the log of the Wheatley #1 well, located C-NE-SW of Section 23-33S-31W, Seward County, Kansas.

PANHANDLE DEVELOPMENT CO., INC.

B. Lynn Herington  
Accountant

Subscribed and sworn to before me a notary public this 20 day of June, 1962

Dean Jaye Hefner  
Notary Public

My Commission Expires June 16, 1963.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 18 1962

CONSERVATION DIVISION  
Wichita, Kansas