

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20,405
LEASE NAME CAMPBELL "A"
WELL NUMBER 1
SPOT LOCATION C SE SW
SEC. 18 TWP 33S RGE. 34 (E) or (W)
COUNTY Seward
Date Well Completed 6/29/79
Plugging Commenced 11/19/84
Plugging Completed 11/21/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Production Company
ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 5469

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #1 (Rep. Paul Luthi)

Is ACO-1 filed? C-10 If not, is well log attached? NA

Producing formation Chester Depth to top 6198' bottom 6206' T.D. 6363'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Chester	Oil	6198	6206	8-5/8"	1686'	-0-
				5-1/2"	6317'	1674'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pumped 25 sx cmt, 1-1/2 sx hulls to 6198'. Shot off 5-1/2" casing at 2577', pulled 20', pipe stuck, left strain on pipe overnight. Pumped 40 sx cmt to 2557', shot off pipe at 1674', pumped 25 sx cmt, pulled pipe to 640', pumped 20 sx cmt, pulled pipe to 40', pumped 10 sx cmt 40' to 3'. Pulled total of 1674' of 5-1/2" casing. Cut off 8-5/8" casing 3' below ground level and capped well. The hole was kept full of mud at all times.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547
Address 620 S. Lincoln, Liberal, Kansas 67901

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF SEWARD, ss.

Paul Campbell (employee of operator) or DEC 17 1984

~~operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and CONSERVATION DIVISION
the log of the above-described well as filed that the same are true and correct, so help me God. Wichita, Kansas

(Signature) Paul Campbell

(Address) P. O. Box 351, Liberal, KS 67901

SUBSCRIBED AND SWORN TO before me this 13th day of December, 1984
BEVERLY J. WILLIAMS
Seward County, Kansas
My Comm. Exp. November 21, 1986

Beverly J. Williams
Notary Public

My Commission expires November 21, 1986