

15-175-20126-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20,126

LEASE NAME McGee

WELL NUMBER 1

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 18 TWP. 33S RGE. 34W (N) or (W)

COUNTY Seward

Date Well Completed 12-5-70

Plugging Commenced 7-06-89

Plugging Completed 7-08-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Co.

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE#(918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/8/89 (date)

by n/a (KCC District Agent's Name).

Is ACO-1 filed? on old form If not, is well log attached? -

Producing Formation Toronto Depth to Top 4239 Bottom 4242 T.D. 6500

Show depth and thickness of all water, oil and gas formations.
LKC 4842 4873

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Toronto</u>	<u>GAS</u>	<u>4239</u>	<u>42</u>			
<u>LKC</u>	<u>"</u>	<u>4842</u>	<u>73</u>	<u>8 5/8</u>	<u>1,686'</u>	<u>NONE</u>
				<u>5 1/2"</u>	<u>4,930'</u>	<u>2,625.45'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

CIBP 4,700' w/15' cement. CIBP 4,200' w/15' cement.
30 sack cement stub plug 2440'-2200'.
40 sack cement plug from 1,720' to 1,620'
25 sack cement plug @ 800'-710'. 10 sack cement plug from 40' to 4'
(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Reeves Casing License No. 3003

Address P. O. Box 94204, Oklahoma City, Oklahoma 73143

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: KAISER-FRANCIS OIL CO.

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P.O. Box 21468, Tulsa, OK

SUBSCRIBED AND SWORN TO before me this 27th day of July, 19 89

Brenda Bowles
Notary Public

My Commission Expires: June 27, 1990

