

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20327-00-00

LEASE NAME GUTTRIDGE

WELL NUMBER A-3

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 19 TWP. 33S RGE 34 (X) or (W)

COUNTY SEWARD

Date Well Completed 11-1-1977

Plugging Commenced 2-27-03

Plugging Completed 2-28-03

RECEIVED

MAR 10 2003

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-20-03 (date)

by KEVIN STRUBE (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation CHESTER Depth to Top 6236 Bottom 6253 T.D. 6550

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHESTER	OIL	6236	6253	8 5/8	1677	0
				5 1/2	6533	2502

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. PLUG PERES WITH 25 SXS CMT AND 400# HULLS. RU JACKS AND SHOOT OFF 5-1/2 CSG AT 2502. PULL CSG TO 1700 AND SPOT 50 SXS CMT FROM 1700 TO 1550. PULL CSG TO 600 AND SPOT 40 SXS CMT FROM 600 TO 480. PULL CSG TO 40 AND SPOT 10 SXS CMT FROM 40 TO 3. CUT OFF AND CAP 8 5/8 CSG 3 BELOW GL. RDMQ.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION


STATE OF TEXAS COUNTY OF POTTER, ss.

CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters
CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101

SUBSCRIBED AND SWORN TO before me this 6 day of March, 2003



Lori Pearson
Notary Public

My Commission Expires: 2/26/05