

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 1517520453 00-00

LEASE NAME COSGROVE

WELL NUMBER A-3

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 22 TWP. 33 RGE 34 (X) or (W)

COUNTY SEWARD

Date Well Completed 4-26-1980

Plugging Commenced 4-22-2003

Plugging Completed 4-26-2003

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-21-2003 (date)

by RICHARD LACEY (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation L MORROW / CHESTER Depth to Top 5873 Bottom 5910 T.D. 6360

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
L MORROW	OIL	5873	5880	8 5/8	1679	0
CHESTER	OIL	5900	5990	4 1/2	6357	1685

RECEIVED
MAY 07 2003
KCC WICHITA

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. PUMP 2 SXS HULLS AND 20 SXS CMT TO PLUG PERFS. SHOOT OFF 4 1/2 CSG AT 1685. SPOT 50 SXS CMT FROM 1685 TO 1535. SPOT 40 SXS CMT FROM 700 TO 850. SPOT 10 SXS CMT FROM 40 TO SURFACE. CUT OFF AND CAP 8 5/8 CSG 3 BELOW GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.

CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters
CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101

SUBSCRIBED AND SWORN TO before me this 1 day of May, 2003

Lori Pearson

My Commission Expires: 2/26/05

