

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20378 - 00-00

LEASE NAME FINCHAM

WELL NUMBER D-1

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 29 TWP. 33 RGE 34 (E) or (W)

COUNTY SEWARD

Date Well Completed 12-5-1978

Plugging Commenced 6-26-2002

Plugging Completed 6-27-2002

RECEIVED

AUG 08 2002

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-21-2002 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation CHESTER Depth to Top 6253 Bottom 6276 T.D. 6370

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHESTER	OIL	6253	6276	8 5/8	1699	0
				5 1/2	6360	2221

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. SET CIBP @ 5900. DUMP 2 SXS CMT. SHOOT OFF 5 1/2 CSG AT 2221. PLUG 1730-1580 WITH CMT. PLUG 600 TO 480 WITH CMT. PLUG 40 TO SURFACE WITH CMT. CUT OFF AND CAP 8 5/8 CSG 4 FEET BELOW GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.

CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters

CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101



SUBSCRIBED AND SWORN TO before me this 6 day of August, 20 02

Lori Pearson
Notary Public

My Commission Expires: 2/26/05

OR