

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-175-21100

MB

API NUMBER 15-172-21,100-0000

LEASE NAME Rowland "A"

WELL NUMBER 1H

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4030 Ft. from S Section Line

4030 Ft. from E Section Line

SEC. 23 MB 7 TWP. 33S RGE. 34 ~~XXX~~ (W)

LEASE OPERATOR Anadarko Petroleum Corporation

COUNTY Seward

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

Date Well Completed 7/5/90

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Plugging Commenced 11/18/94

Character of Well Gas

Plugging Completed 11/22/94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/22/94 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation None Depth to Top _____ Bottom _____ T.D. 2974

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	660'	3'
				5 1/2	2974'	772'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU Sargents. Pmp 2 sxs hulls & 25 sxs cmt from 2634-2500'. Fell to 2680'. Pmp 3 sxs hulls & 25 sxs cmt from 2634-2500'. Tag cmt @ 2640. Pmp 2 sxs hulls & 25 sxs cmt from 2634-2500'. Shot 5 1/2" csg @ 772'. Pmpd 50 sxs cmt plug @ 700-550'. Pmp 10 sxs cmt plug @ 40-3'. Rec 18 jts 5 1/2" csg. Cut off 8 5/8" csg 3' below gl & cap. Witnessed by KCC Rep - Glenn Barlow.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Rt 1, Box 49BA, Tyrone, OK 73951-9731 (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.


Leslie I. Barnes, Sr. Technical Assistant (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well was filed that the same are true and correct, so help me God.

(Signature) Leslie I. Barnes

Leslie I. Barnes, Sr. Tech. Asst.

(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 7th day of December, 1994



Notary Public

My Commission Expires _____