

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20,525-0000

LEASE NAME Maxwell "B"

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 23 TWP. 33S RGE. 34 ~~XXX~~ or (W)

COUNTY Seward

Date Well Completed 5-28-81

Plugging Commenced 11-1-90

Plugging Completed 11-2-90

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 17, 1990 (date)

by Glen Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Chester Depth to Top 6234 Bottom 6241 T.D. 6400

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 1674 | |
| | | | | 4 1/2 | 6399 | 2856 |
| | | | | 2 3/8 | 6200 | 6200 |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 60 sxs of cmt from 2830 to 2600. Pump 50 sxs of cmt from 1700 to 1500.
Pump 30 sxs of cmt from 700 to 600. Put 10 sxs of cmt from 40 to 0. Cut off 8-5/8 csg 3'
below ground level and weld on cap. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address P.O. Box 506, Liberal, Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss. FEB 11 1991

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams

(Address) Beverly J. Williams, Eng. Tech.
P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 8th day of February, 19 91

Cheryl Steers
Notary Public

My Commission Expires: _____

