

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Seward SEC. 28 TWP. 33S RGE. 34 XX/W
 Location as in quarters or footage from lines:
SW of NE/4

		28	

Lease Owner Anadarko Production Company
 Lease Name Nix "E" Well No. 1
 Office Address Box 351, Liberal, Kansas 67901
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 7-26-82
 Application for plugging filed March 4, 1982
 Plugging commenced 7/25/82
 Plugging completed 7/26/82
 Reason for abandonment of well or producing formation No producing formation

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Paul Luthi

Producing formation None Depth to top _____ bottom _____ T.D. 6435

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	1702	0	1702	8-5/8	1702	0
Production	6128	0	6128	4-1/2	6128	4522

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Mixed 35 sxs cmt, pumped and plugged 5850 BTM, cmt 5970 w/heavy drilling mud, cmt plug 5850 to 6055, shot off 4-1/2 casing at 4522', Pulled casing to 2400', 35 sxs, cmt plug 2400-2300', Pulled casing to 1750', spotted 40 sxs cmt 1750' to 1650', Pulled casing to 800', spotted 25 sxs cmt, plug 800-700', all plugs were displaced w/heavy drilling mud.

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 10 1982
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Sargent Casing Pulling Service

STATE OF Kansas COUNTY OF Seward, ss.
G. B. Smith (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) G. B. Smith
Box 351, Liberal, Kansas 67901
 (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of July, 19 82

My Commission expires:

STATE NOTARY PUBLIC
 ELIZABETH J. HOOPER
 Seward County, Kansas
 My Appl. Expires 7-26-83

Elizabeth J. Hooper
 Notary Public.

JOHNSON *Drilling Company, Inc.*



OFFICES IN
EVANSVILLE, INDIANA
TEL. (812) 424-8291
OKLAHOMA CITY, OKLAHOMA
TEL. (405) 943-7667
LIBERAL, KANSAS
TEL. (316) 624-7731

REPLY TO:

3535 N.W. 58th Suite 710
Oklahoma City, Oklahoma 73112

December 31, 1980

ANADARKO PRODUCTION COMPANY
P.O. BOX 351
LIBERAL, KANSAS 67901

ATTEN: PAUL GATLIN

Drillers Log For:

0' - 280'
280' - 532'
532' - 1693'
1693' - 1703'
1703' - 2307'
2307' - 6435'

Nix E #1
Surface, Clay and Sand
Clay and Sand
Redbed and Sand
Anhydrite
Shale
Lime and Shale

JOHNSON DRILLING COMPANY, INC.

SIGNED BY:

Claude D. Moore

CLAUDE D. MOORE MANAGER

STATE OF OKLAHOMA
COUNTY OF OKLAHOMA

Subscribed and sworn to before me this 31st day of December, 1980.

Paul Wicks

NOTARY PUBLIC

My Commission Expires: _____

My Commission Expires May 14, 1984

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1982
CONSERVATION DIVISION
Wichita, Kansas