


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Meade County, Sec. 3 Twp. 33 Rge. 30 (E) (W) X
Location as "NE/CNW/SW" or footage from lines G SE NW
Lease Owner McAdams Pipe & Supply Co.
Lease Name Leslie "A" Well No. 1
Office Address Drawer 960 Bristow, Oklahoma 74010
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Sept. 13 1956
Application for plugging filed March 11 1974
Application for plugging approved March 13 1974
Plugging commenced 5-1 1974
Plugging completed 5-4 1974
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production - 5-10 1973
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves
Producing formation Morrow Depth to top 5659 Bottom 5667 Total Depth of Well 5820
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8	672	none
				8 5/8	2660	853
				5 1/2	5800	3834

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pump 20 sks. of Cement to 5550
Pump 50 sks. of Cement @ 600 to 500
Put 20 sks. of Cement @ 40 to 0

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1974

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Sargents Casing Pulling Service Kansas No. 511
Address Box 506 Liberal, Kansas 67901

STATE OF Oklahoma COUNTY OF Cheek
T. P. McAdams, Jr. (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

P.O. Box 960 Bristow, OK (Address)

SUBSCRIBED AND SWORN TO before me this 13 day of May 1974

My commission expires September 23, 1975

Notary Public.


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- COLORADO OIL & GAS
Farm- Leslie "A" No. 1

SEC. 3 T. 33 R. 30W
C SE/4 NW/4

Total Depth. 5820'
Comm. 7-29-55. Comp. 9-4-55
Shot or Treated.
Contractor.
Issued. 10-29-55

County Meade KANSAS



Elevation. 2736'

Production. 1056 BOPD

Figures indicate Bottom of Formations.

CASING:	
13"	682'
8"	2660'
5"	5800'
sand, shells	650
red rock	700
red rock & sand	950
red rock, sand,	
shells	1345
red rock shells	1470
anhydrite	1631
shale, shells	1650
red rock, salt	1720
shale	1740
shale, lime	1959
shale	1980
shale, lime	2230
shale, anhydrite	2300
shale, lime	2380
anhydrite, shale	2440
shale, lime	2515
lime	2534
shale, lime	2560
lime	2612
dolomite	2624
lime	2662
lime, shale	2865
lime	3105
lime, chalk	3245
chalky lime & lime	3330
lime	3395
lime, shale	3521
lime	3942
lime, shale	4025
lime	4058
lime, chat	4109
lime, shale	4240
lime	4323
lime, shale	4505
lime	4550
chert, lime	4830
chert, shale	4875
lime	4930
lime, shale	5165
lime	5340
lime, shale, chert	5353
lime, shale	5400
lime	5455
lime, shale, chert	5477
lime	5623
coring	5656
reaming cor hole	5656
coring	5759
lime	5820
Total Depth	
Tops: Scout	
Lansing	4532
Morrow Shald	5620
Morrow Sand	5659

RECEIVED
STATE CORPORATION COMMISSION
MAR 13 1974
CONSERVATION DIVISION
Wichita, Kansas