


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Meade County, Sec. 4 Twp. 33S Rge. (E) 30 (W)
Location as "NE/CNW/SW" or footage from lines C-NE-NE-SE
Lease Owner Sunray Mid-Continent Oil Company
Lease Name Ruby Richardson Well No. 1
Office Address Box # 788, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 18, 19 55
Application for plugging filed October 18, 19 55
Application for plugging approved October 19, 19 55
Plugging commenced January 25, 19 57
Plugging completed January 30, 19 57
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation Depth to top Bottom Total Depth of Well 5825' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13-3/8"	624'	None
				8-5/8"	2709'	679'
				Plugged back to 5600' with 75 sacks of cement.		
				Plugged back from 2725' to 2680' with 15 sacks of cement.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand from 2680' to 2660' and ran 5 sacks of cement. Mudded hle to 550', set a rock bridge and ran 30 sacks of cement. Mudded hole to 20', set a rock ~~BRIDGE~~ bridge and ran 20 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company, Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
N. E. Montgomery (employee of owner) or (owner/proprietor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) N. E. Montgomery
Box # 788, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4 day of February, 19 57

My commission expires Dec. 24, 1960

Notary Public. STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 4 T 33 R 30W
BOOK PAGE 128 LI E 35

FEB - 5 1957
CONSERVATION DIVISION
Wichita, Kansas

Sunray Mid-Continent Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
October 24, 1955

CONTRACTOR: STECKLE Drilling Company
Drilling commenced: September 12, 1955
Drilling completed: October 10, 1955

Ruby Richardson #1 S/2
Sec. 4-33S-30W, Meade
County, Kansas.

DRILLERS LOG

0-290	Sand & Shale
290-450	Sand
450-625	Clay & Shale
625-910	Red Bed
910-1175	Red Bed & Shells
1175-1380	Red Bed
1380-1490	Red Bed & Shells
1490-1535	Anhydrite
1535-1640	Shale & Shells
1640-1735	Red Bed
1735-1933	Shale & Shells
1933-2020	Red Bed
2020-2109	Shale Lime & Shells
2109-2172	Shale & Shells
2172-2275	Red Bed
2275-2385	Lime Shells & Shale
2385-2505	Lime & Shale
2505-2635	Lime
2635-2710	Lime & Shale
2710-2835	Shale & Lime
2835-2990	Lime & Shale
2990-3030	Lime
3030-3235	Lime & Shale
3235-3545	Crabby Lime
3545-3640	Lime
3640-4217	Lime & Shale
4217-4280	Lime Gray
4280-4382	Shale & Lime
4382-4535	Lime & Shale
4535-4967	Lime
4967-5191	Lime & Shale
5191-5227	Lime & Junk
5227-5255	Lime
5255-5315	Lime & Shale
5315-5340	Lime
5340-5463	Lime & Shale
5463-5485	Lime
5485-5534	Shale & Lime
5534-5806	Lime & Shale
5806-5825	Miss. Dolomite

I, Lillian T. Bonham hereby certify the above to be a complete
Drillers Log of Sunray Mid-Continent Oil Company's Ruby Richardson
#1 S/2 Section 4-33S-30W, Meade County, Kansas.

RECEIVED
Lillian T. Bonham
STATE CORPORATION COMMISSION

FEB - 5 1957

Notary Public

CONSENT AND DIVISION

COMMISSION Expires

PLUGGING
FILE SEC. 4 T 33 R 30W
BOOK PAGE 138 LINE 35