

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Meade County. Sec. 6 Twp. 33 Rge. 30 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW/NW/NE

Lease Owner Shamrock Oil & Gas Corporation

Lease Name Collinswood Well No. #1

Office Address Box 63, Amarillo, Texas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed Yes 19

Application for plugging approved Yes 19

Plugging commenced 8-31 19 57

Plugging completed 9-5 19 57

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Mr. M.A. Rives

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 5650' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"		4554'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measured into TD 5650'.
Plugging started 8-31-57. Finished 9-5-57.
Shot 7" casing at 4554'. Pulled pipe out of hole and plugged well with heavy mud to 650'. Set permanent rock bridge. Dumped 25 sacks cement. Filled hole with mud to 30' and mixed 10 sacks for cap on well. Well completed.

STATE CORPORATION COMMISSION
SEP 10 1957
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor J.O. Forbes (If additional description is necessary, use BACK of this sheet)
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
[Address] Box 221, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 9th day of September, 1957.

My commission expires November 8, 1960. [Signature] Notary Public.

PLUGGING
FILE SEC. 6 T. 33 R. 30W
BOOK PAGE 40 LINE 36

COLLINGWOOD # 1
 SEC. 6. TWP. 33 S. RANGE 30 W.
 MEADE COUNTY, KANSAS

0	-	160'	SURFACE & CLAY
160'	-	975'	SAND, SHALE, SHELLS
975'	-	2220'	SHALE & SHELLS
2220'	-	2400'	LIME & SHALE
2400'	-	2600'	ANHYDRITE
2600'	-	2645'	DOLOMITE & ANHYDRITE
2645'	-	2900'	DOLOMITE
2900'	-	3600'	LIMESTONE
3600'	-	3610'	SAND
3610'	-	3755'	LIMESTONE
3755'	-	3790'	SHALEY LIMESTONE
3790'	-	3800'	LIMESTONE
3800'	-	3850'	SHALEY LIMESTONE
3850'	-	3875'	LIMESTONE
3875'	-	3890'	SHALE
3890'	-	3905'	LIMESTONE
3905'	-	3915'	SHALE
3915'	-	3965'	LIMESTONE
3965'	-	4000'	SHALE
4000'	-	4020'	SHALE & LIME
4020'	-	4155'	LIMESTONE
4155'	-	4190'	SANDY LIMESTONE
4190'	-	4250'	LIMESTONE
4250'	-	4305'	SHALE
4305'	-	4345'	LIMESTONE
4345'	-	4395'	SHALE
4395'	-	4445'	LIMESTONE
4445'	-	4465'	SHALE
4465'	-	4925'	LIMESTONE
4925'	-	4950'	SHALE & LIME
4950'	-	5045'	LIMESTONE
5045'	-	5355'	SHALE & LIME
5355'	-	5400'	LIMESTONE
5400'	-	5690'	SHALE & LIME
5690'	-	5695'	SHALE

PLUGGING

FILE SEC 6 T. 33 R. 30W
 BOOK PAGE 40 LINE 36

STATE OF KANSAS
 DEPARTMENT OF GEOLOGY

APR 19 1911

CONFIDENTIAL