

15-119-10065-0001

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-OWWO

LEASE NAME Jennings 9

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div. C  
office within 30 days.

SW NE Ft. from S Section Line

Ft. from E Section Line

SEC. 9 TWP. 33S RGE. 30W (E) or (W)

COUNTY Meade

LEASE OPERATOR Sage Drilling Co., Inc.

ADDRESS 202 S. St. Francis Wichita, Kansas 67202

PHONE # 316) 263-6139 OPERATORS LICENSE NO. 5421

Date Well Completed 3-30-83

Character of Well Oil

Plugging Commenced 8-26-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-30-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Marmaton Depth to Top 5146' Bottom 5151 T.D. 5400

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				13 3/8	631	none
				8 5/8	2689	999
				4 1/2	5318	4370

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

CIBP @ 5196' Pump 15 sks. of cement @ 4885 Pump 25 sks. of cement @ 2740

Pump 50 sks. of cement @ 650

Put 25 sks. of cement @ 40 to 0 9 ppg mud is between all plugs

Cut off & cap 8 5/8 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 South Lincoln Liberal, Kansas 67901


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Charles Casey Coats, P.E. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles Casey Coats, P.E.

(Address) 202 S. St. Francis, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 16 day of September, 19 85



RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public  
Sandra Kay Woosypiti  
SEP 17 1985

My Commission Expires: June 5, 1988

CONSERVATION DIVISION  
Wichita, Kansas

Form CP-4  
Revised 08-84