

KS CORP COMMISSION
WICHITA ST OFFICE BLDG
130 S MARKET, ROOM 2078
WICHITA KS 67202

WELL PLUGGING RECORD

API NUMBER 175-21602-00-00

LEASE NAME C6lburn

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.
RECEIVED

WELL NUMBER 3-21

SPOT LOCATION NE-NW-NW
230' N of

LEASE OPERATOR MIDWESTERN EXPLORATION COMPANY

OCT 31 2003
10-31-03

SEC. 21 TWP. 33S RGE. 32 (E) OR (W)

ADDRESS 3500 S. Boulevard/Suite 2B
Edmond, Oklahoma 73013

KCC WICHITA COUNTY Seward

PHONE # (405) 340-4300

OPERATORS LICENSE NO. 5263

DATE WELL COMPLETED 3-13-97

PLUGGING COMMENCED 10-15-03

CHARACTER OF WELL gas
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

PLUGGING COMPLETED 10-21-03

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City

IS ACO-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION Herrington
Keider Winfield DEPTH TO TOP 2426 BOTTOM 2512 T.D. 3150

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Herrington	gas oil water	2426	32	8 5/8"	572'	0'
Krider	gas oil water	2458	73	4 1/2"	2982'	1100'
winfield	gas oil water	2496	2512			

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Pulled rods & tubing. Displaced hole with 45 bbls mud set CIBP @2380' with 2 sx. cement on top. Cut casing off @1431' & could not circulate @ 1400'. Pulled pipe up to 1100'. Circulate hole with mud. Pump 50 sx. cement from 1100 to 950'. Pull up to 40'. Pump 20 sx. cement to surface. Cut off 4' BGL welded ID plate.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Jerry Dunkin, Inc. LICENSE No. 8733
ADDRESS P.O. Box 389 Enid, Oklahoma 73702

STATE OF Oklahoma COUNTY OF Oklahoma SS.

Dale J. Lollar, President, Midwestern Exploration Co (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Dale J. Lollar

(ADDRESS) 3500 S. Boulevard, Ste. 2-B
Edmond, OK. 73013



VIRGINIA MEANS
Oklahoma County
Notary Public in and for
State of Oklahoma
My commission expires July 12, 2005.

SUBSCRIBED AND SWORN TO BEFORE ME THIS 29th DAY OF October 2003

Virginia Means
NOTARY PUBLIC

MY COMMISSION EXPIRES: July 12, 2005