

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER TA # 1-175-051

LEASE NAME Hay's

WELL NUMBER #2

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. \_\_\_ TWP. \_\_\_ RGE. \_\_\_ (E) or (W)

COUNTY Seward

Date Well Completed 1961

Plugging Commenced 4-13-92

Plugging Completed 4-16-92

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR A.L. Abercrombie Inc.

ADDRESS RT #1 Box 56, Great Bend, Kansas, 67530

PHONE#(316) 793-8186 OPERATORS LICENSE NO 5393

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-13-92 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filled? ? If not, Is well log attached? NO

Producing Formation \_\_\_\_\_ Depth to Top 4431 Bottom 4490 T.D. 5926

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>8 3/8</u>	<u>1241</u>	
				<u>5 1/2</u>	<u>5908</u>	<u>2589</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.  
Push Plug to 4430 - Sanded Back to 4380' & Dump Bailed 5 SX Cement. Layed out Casing & Plug with 10 SX Gell - 300 LBS Hulls - 50 SX Cement - 10 SX Gell - 100 LBS Hulls - Wiper Plug and 120 SX Cement - 60/40 Poz. mix. 60 to Gell - Halco Ticket no 216616 Plug Down @ 12115 - 4-16-92

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pipe Recovery Inc. License No. 30752

Address P.O. Box 7, Great Bend, Kansas, 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: \_\_\_\_\_

STATE OF Kansas COUNTY OF Kansas, ss.

Rich Davis

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) Rich Davis  
(Address) P.O. Box 7, Great Bend, Kansas



SUBSCRIBED AND SWORN TO before me this 20th day of \_\_\_\_\_, 1992

Bartow Co Ks Richard L. Davis  
Notary Public

Commission Expires: 11-19-1995

RECEIVED  
STATE CORPORATION COMMISSION  
APR 23 1992  
4-23-92  
CONSERVATION DIVISION  
Wichita, Kansas

HAYS NO. 2  
Panhandle Development Company, Inc.  
Section 35-33s-31w  
Seward County, Kansas

Casing Record:

8 5/8" O.D. at 1243.90 G.L. with 500 sacks  
Pozmix 2% CC, 200 sacks common 2% CC, 5 1/2"  
O.D. at 5908' K.B. with 75 sacks Pozmix,  
salt saturated. T.V. collar at 4533'  
Top stage with 125 sacks Pozmix, salt  
saturated.

Commenced: 10-17-61

Completed: 11-09-61

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Top Soil	0	160
Sand, Shells & Red Bed	160	950
Red Bed and Sand	950	1260
Red Bed	1260	1410
Red Bed & Anhydrite	1410	1790
Red Bed & Lime Shells	1790	2050
Shale & Lime	2050	2215
Anhydrite & Shale	2215	2380
Lime & Shale	2380	4442
Lime	4442	5473
Lime & Shale	5473	5551
Lime	5551	5635
Lime & Shale	5635	5730
Lime	5730	5915 RTD

State of Kansas )  
County of Seward ) SS

I Hereby affirm that the above and foregoing is a true and correct copy of the log of the Hays No. 2 well, located C-NW-SE of Section 35-33s-31w, Seward County, Kansas.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 26 1992  
CONSERVATION DIVISION

McCLELLAN DRILLING COMPANY

by [Signature]  
Manager

Subscribed and sworn to before me a notary public this 10<sup>th</sup>  
day of November, 1961.

[Signature]  
Notary Public - Seward County, Kansas

My Commission Expires:  
September 26, 1965