

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION
170 S. Market, Room 2078
Wichita, KS 67202

K.A.R.-82-3-117

API NUMBER 15-119-20961-00-00

LEASE NAME BROMWELL "A"

WELL NUMBER 1-13

TYPE OR PRINT
NOTICE- Fill out completely
and return to Cons. Div.
office within 30 days.

4620 Ft. from S Section Line

1500 Ft. from E Section Line

LEASE OPERATOR McCoy Petroleum Corporation

SEC. 13 TWP. 33s RGE. 30w E W

ADDRESS 3017 N. Cypress Street, Wichita, KS 67226-4003

COUNTY Meade

PHONE # (316) 636-2737 OPERATORS LICENSE NO. 5003

Date Well Completed 5/23/96

Character of Well P&A

Plugging Commenced 11/20/97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11/26/97

The plugging proposal was approved on 8/28/97 (date)

by Richard Lacey (KCC District Agent's Name),

Is ACO-I filed? Yes If not, Is well log attached?

Producing Formation None Depth to Top Bottom T.D. 5920'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		0	1591'	8 5/8"	1591'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

11/21/97: P&A using Premium Cmt., 6% Gel: Set CIBP at 4770' & cap with 2 sks cmt. Bailed cement at 4770'. Shot at 3620' & 3417'. Pulled to 1628' Pumped 50 sks cement with 1 hull and displaced with 2 gel and 4 bbls water. Pulled to 650'. Pumped 50 sks cmt & 1 hull displaced with 2 gel & 4 bbls water. Pulled to 40'. Pumped 10 sks cmt and laid down last joint. Cement dropped 1596' overnight. 11/25/97: Pumped 50 sks @ 1596' and plug, 25 sks @ 635 and plug, 10 sks up to 40' and plug, plug at surface. Cement held. Orders by Gary Winter - KCC.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor 11/21/97: Quality Well Service, Inc. (31925) License No. 11/25/97: Post & Mastin Well Service (8438)

Address Quality Well Service, Inc. 249 Beth Dr., Sterling KS 67579-9048 / Post & Mastin Well Service, Inc. Box 297, Garden City, KS 67846

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES McCoy Petroleum Corporation

STATE OF Kansas COUNTY OF Sedgwick ss.

Brent B. Reinhardt, Regulatory Geologist, (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Brent B Reinhardt

(Address) 3017 N. Cypress Street, Wichita, KS 67226-4003

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 97

Deborah Ann Paulus
Notary Public

My Commission Expires January 8, 2000

