

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Midwestern Exploration Co

ADDRESS PO Box 1884 Liberal KS 67905-1884

PHONE# (316) 624-3534 OPERATORS LICENSE NO. 5263

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-31-95 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation CHASE Depth to Top 2596' Bottom 2606' T.D. 3150'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
HENNINGTON	GAS & WATER	585	0	8 5/8	585	-0-
KNIDEN	GAS & WATER	3150	0	4 1/2	3150	2120
FT. KILBY	WATER					
COUNCIL GROVE	WATER					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from _____ feet to _____ feet each s
Mixed 1 sk hulls to 20 sk cmt. to plug perfs from 2596 to 2396. Shot 4 1/2 loose @ 2323. Pulled to 1490. Mixed 50 sk cmt. plug from 1490 to 1340. Pull 4 1/2 to 1230 where it stuck. Shot loose @ 1021 & pulled to 610. Mixed 50 sk cmt plug @ bottom of 8 5/8 from 610 to 460. Mixed 10 sk plug from 40 to 0. Cut off to cap 3ft. below ground level.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MIDWESTERN EXPLORATION COMPANY

STATE OF KANSAS COUNTY OF SEWARD, ss.

CHUCK REDMON (Employee of Operator) (Operator above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Chuck Redmon

(Address) P.O. Box 1884 LIBERAL, KS 67901-1884



SUBSCRIBED AND SWORN TO before me this 7th day of November, 19 95

Virginia Means
 Notary Public
 My Commission Expires: March 10, 1999