

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20841-0000

LEASE NAME Arkalon

WELL NUMBER 1-27

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4620 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 27 TWP. 33S RGE. 32 ~~32~~ (W)

COUNTY Seward

Date Well Completed 3-26-85

Plugging Commenced 3-26-85

Plugging Completed 3-26-85

LEASE OPERATOR Jack Reese dba Midwestern Exploration

ADDRESS P.O. Box 1884, Liberal, KS 67901

PHONE# (316) 624-3534 OPERATORS LICENSE NO. 5263

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? No If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 6244

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface Csg				8-5/8	1557	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well w/125 sx 60/40 pos w/2% gel. 3% cc as follows: 50 sx @ 1620; 40 sx @ 600'; 10 sx @ 40' w/solid bridge and wiper plug. 15 sx rathole, 10 sx mousehole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. RECEIVED 5287

STATE CORPORATION COMMISSION

Address West 54 Highway, Liberal, KS 67901


STATE OF Kansas COUNTY OF Seward, ss. APR 30 1985

Harold K. Frauli (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Harold K. Frauli

(Address) P.O. Box 1884, Liberal, KS 67901

SUBSCRIBED AND SWORN TO before me this 11th day of April, 19 85



Elaine Long
Notary Public

My Appointment Expires: _____

DRILLER'S LOG

Jack Reese d/b/a Midwestern Exploration
 P O Box 1884
 Liberal, Ks. 67901

Surface Casing: Ran 8 5/8" casing 37 jts. 8 5/8
 24" -J-55 shoe @ 1557 . Cement same & circ. Cmt.-
 w/ Dowell w/550 sx lite w/2% cc F/by 200 sx class
 H w/3% CC

Commenced: 3-5-85
 Completed: 3-26-85

Total Depth: 6244

FORMATION	FROM	TO	REMARKS
Sand	0	420	LTD 6237
Red Bed	420	694	
Red Bed, Sand & Anhydrite	694	1195	
Red Bed, Sand & Anhydrite	1195	1500	
Red Bed & Anhydrite	1500	1558	
Plug & Cement	1558	1558	
Sand & Shale	1558	2035	
Shale	2035	2290	
Shale	2290	2621	
Lime & Shale	2621	2845	
Lime & Shale	2845	3515	
Shale	3515	3702	
Shale & Lime	3702	6012	
Lime & Shale	6012	6095	
Lime	6095	6244	

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.

NRG Drilling, Inc.

By Elmer Jack Taylor
 Elmer Jack Taylor

Subscribed and sworn to before me this 28 day of March 19 85

Lexanna L. Allen
 Lexanna L. Allen

RECEIVED
 STATE CORPORATION COMMISSION

My commission expires: April 6, 1988

APR 30 1985

CONSERVATION DIVISION
 Wichita, Kansas