

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-175-20,585-0000

LEASE NAME Ingram

WELL NUMBER 1

SPOT LOCATION C NW NW

SEC. 24 TWP. 33 RGE. 32 or (W)

COUNTY Seward

Date Well Completed 5-10-82

Plugging Commenced 6-19-84

Plugging Completed 6-20-84

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Funk Exploration, Inc.

ADDRESS 210 W. Park Ave. - Suite 1000, Oklahoma City, OK 73102

PHONE #(405) 235-2640 OPERATORS LICENSE NO. 6979

Character of Well Gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Attached If not, is well log attached? \_\_\_\_\_

Producing formation Chester Depth to top 5754 bottom 5824 T.D. 6290

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
13 finger		5539	5619	20"	77'	3'
Morrow		5619	5754	8-5/8"	1491'	3'
Chester		5754	5952	4-1/2"	6288	3052'
St. Louis		5952	6105			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Load hole w/9.5ppg mud. Set CIBP @ 5739'. Dump 2 sacks cement w/bailer on CIBP. Free point csg. Cut off csg. @ 3050'. Load hole w/9.5 ppg. mud. Spot 50 sacks Class H cement plug from 1400 to 1540'. Spot 40 sacks Class H cement plug from 760' to 650'. Spot 10 sack Class H cement plug from 3' to 40'. Cut off casing at 3'.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Art's Well Service License No. 1471

Address \_\_\_\_\_  
**RECEIVED**  
STATE CORPORATION COMMISSION

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss. AUG 24 1984

Robert S. Mitchell (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: Wichita, Kansas  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

(Signature) Robert S. Mitchell

(Address) 210 W. Park Ave. - Suite 1000  
Oklahoma City, OK 73102

SUBSCRIBED AND SWORN TO before me this 22<sup>nd</sup> day of August, 1984

Almond Stewart  
Notary Public

My Commission expires: October 16, 1985