

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-175-21,000 - 0000

LEASE NAME Frazier "B"

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1

4620 Ft. from S Section Line

4620 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 1 TWP. 33 SRGE. 33 ~~SEE~~ (W)

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

COUNTY Seward

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 6/7/88

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

RECEIVED  
 STATE CORPORATION COMMISSION

Plugging Commenced 10/9/88

Plugging Completed 10/11/88

The plugging proposal was approved on 8/23/88 (date)

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Hugoton Depth to Top 2522 Bottom 2595 T.D. 7310

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In 1541-Surf	Pulled out
<u>Hugoton</u>	<u>Gas</u>	<u>2522</u>	<u>2595</u>	<u>8-5/8"</u>	<u>2/19/88</u>	<u>0'</u>
				<u>5-1/2"</u>	<u>2689</u>	<u>915' 10/11/88</u>
					<u>3/11/88</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pmpd 2 sxs hulls and 22 sxs cement from 2595-2400. Shot off csg at 915'. TOH. Pmpd 50 sxs cement 930-830, 20 sxs cement 530-430, 10 sxs cement 40-0. Cut off and capped well 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pullers License No. 6547

Address P. O. Box 506, Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

M. L. Pease (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

(Address) P. O. Box 351, Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 19th day of December, 19 88

My Commission Expires: \_\_\_\_\_  
Glenna S. Salley Notary Public

