

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-10032 ⁰¹⁰⁰⁶⁻⁰⁰⁰² ~~CC-70~~

LEASE NAME Beck B

WELL NUMBER 2

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 4 TWP. 33S RGE. 33 ~~XXXX~~ (W)

COUNTY Seward

Date Well Completed 5/22/62

Plugging Commenced 4/24/92

Plugging Completed 4/24/92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR OXY USA INC.

ADDRESS P.O. BOX 26100

PHONE# (405) 749-2374 OPERATORS LICENSE NO. 5447

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 19, 1992 (date)

by District #6 (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? Yes

Producing Formation Chase Depth to Top 2542' Bottom 2664' T.D. 6353'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Chase	gas	2542'	2664'	8 5/8"	1584'	
				5 1/2"	6066'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set CIBP @ 2500'. Pmpd 25 sx cmt over plug. RIH w/52 jts of 2 3/8" tbg. Sptd 50 sx cmt (40/60 poz w/6% gel.) from 1613' to 1030'. Pulled tbg to 750' & sptd 50 sx cmt plug from 750' to 175'. Pulled tbg to 60'. Sptd 10 sx cmt from 60' to surface. P & A completed.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bruce Well Service License No. _____

Address Liberal, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA INC.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

VIC TUMLINSON (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. BOX 26100, OKC. OKLAHOMA 73126-0100

SUBSCRIBED AND SWORN TO before me this 11th day of May

Kelly D. Anderson
Notary Public

My Commission Expires: 8/19/95

RECEIVED
CORPORATION COMMISSION
4 1992
Wichita, Kansas
Form CP-4
Revised 05-88