


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Seward County, Sec. 6 Twp. 33 Rge. (E)33 (W)  
Location as "NE/CNW/SW" or footage from lines. C SW SE  
Lease Owner: Texas Energies, Inc.  
Lease Name: Robinson Estate Well No. 1  
Office Address:  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 11-65 19  
Application for plugging filed 2-75 19  
Application for plugging approved 2-19=75 19  
Plugging commenced 2-19 1975  
Plugging completed 2-20 1975  
Reason for abandonment of well or producing formation No Longer Producing  
If a producing well is abandoned, date of last production XXXXXXXXXXXX 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas  
Producing formation Morrow-St. Louis Depth to top 5,660 Bottom 6,115 Total Depth of Well 6319  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		Surface	1,613	8 5/8	1611	none
		Surface	6,179	4 1/2		2620

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pump 50 sks. of cement & 3 sks. of hulls from 6150 to 5550  
Pump 35 sks. of cement from 1000 to 900  
Put 15 sks. of cement from 45 to 0

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 13 1975  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sargents Casing Pullings Service Kansas No. 511  
Address Box 506 Liberal, Kansas 67901

STATE OF Texas COUNTY OF Potter ss.  
L. E. Goeffroy (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
306 Bank of the Southwest Bldg, Amarillo, Tex. 79101  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of March, 1975

My commission expires June 1, 1975 [Signature] Notary Public.

15-175-10043-0000

STENCILED

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

ORIGINAL

MAR 2 1968

COMPANY ROGER C. HANKS


SEC. 6 T. 33 R. 33W

FARM Robinson Est. NO. 1

LOC. C SW SE

TOTAL DEPTH 6312'  
COMM. 12-9-65 COMP. 3-31-66  
SHOT OR TREATED  
CONTRACTOR Moran Bros., Inc.  
ISSUED 3-2-68

COUNTY Seward  
KANSAS



CASING  
20 10  
15 8 5/8 1613' w/760 sx cem.  
12 6  
13 5 1/2 6307' w/100 sx cem.

ELEVATION 2836' KB

PRODUCTION Pmp 27 BOPD,  
TR W (MORR 5664-74) GR  
34.2

FIGURES INDICATE BOTTOM OF FORMATIONS

COMPLETE DRILLERS LOG NOT AVAILABLE.

TOPS: SCOUT  
Heebner 4210  
Lansing 4318  
Morrow 5571  
Chester 5958  
St/ Genevieve 6120  
St. Louis 6238

RECEIVED  
STATE CORPORATION COMMISSION

1 - 8 19 1975

CONSERVATION DIVISION  
Wichita, Kansas