

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Elder & Vaughn, Inc.

ADDRESS P.O. Box 18938, Okla. City, OK 73154

PHONE# (405) 842-8877 OPERATORS LICENSE NO. 7157

Character of Well Dry & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-3-96 (date)

by Steve Phiefer (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>8 5/8</u>	<u>1520</u>	<u>-</u>
				<u>5 1/2</u>	<u>3249</u>	<u>2169</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from _____ feet to _____ feet each s
10-4-96 Mixed 1 SK Hulls + 25 SX cmt to plug perf from 2625 to 2425.
Shot 5 1/2 loose @ 2169 Pulled 5 1/2 to 1550 + circ hole w/mud + mixed 50 sx cmt.
plug from 1550 to 1400 Pulled to 500. 10-7-96 Mixed 50 SX cmt plug from 500 to 350.
Pull to 40. Mixed 10 SX cmt plug 40 to 0. Cut off + cap 8 5/8 3 ft. below ground level.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Elder & Vaughn

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Sock H. Vaughn (Employee of Operator) or (Operator)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the fac
 statements, and matters herein contained and the log of the above-described well as filed i
 the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 18938, Okla. City, OK 73154

Subscribed and sworn to before me this 31st day of Oct, 1996

[Signature]
 Notary Public

