

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Seward County, Sec. 27 Twp. 33S Rge. (E) 31 (W)

Location as "NE/CNW/SW" or footage from lines NW NE NE

Lease Owner Thomas & Brewer

Lease Name Langhofer Well No. 1-27

Office Address Drawer 1248 - Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-2 1960

Application for plugging filed 10-2 1960

Application for plugging approved 10-4 1960


Plugging commenced 10-4 1960

Plugging completed 10-4 1960

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Lac Kamp

Producing formation None Depth to top Bottom Total Depth of Well 3400 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TD	SIZE	PUT IN	PULLED OUT
Dakota	Fresh Water	300'	400'	8 5/8	600'	None
Hugoton Series	Salt Water	2800'	2800'			
Council Grove	Salt Water	3082'	3400'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 600'; 20 sacks cement thru drill pipe @ 600'; heavy mud to 15'; Cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bennett & Roberts

Address Russell, Kansas

STATE OF KANSAS, COUNTY OF SEWARD, ss.

Glenn F. Thomas (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) *Glenn F. Thomas*

(Address)

SUBSCRIBED AND SWORN to before me this 4/4 day of October, 1960

My commission expires Nov 5, 1962

Maxene Keating
Notary Public.



R

THOMAS & BREWER
Langhofer #1-27

NW NE NE of Sec. 27-33-31W
Seward County, Kansas

KTD 3400'

CONTRACTOR: Bennett & Roberts Drilling Co.

Commenced 9/23/60
Completed 10/4/60

Set @ 5/8" @ 600' w/300 sx cmt

Surface Soil & Sand	160'
Sand	285
Shale, Sand	380
Sand	470
Sand & Gravel	580
Red Bed	1005
Sand	1090
Red Bed & Sand	1250
Red Bed, Anhydrite streaks	1515
Red Bed	1550
Anhydrite	1575
Shale & Shells	1919
Lime, Shale & Anhydrite	2075
Lime & Shale	2340
Lime	2600
Lime & Shale	2814
Lime	3090
Lime & Chalk	3400

RECEIVED
STATE DEPT. OF REVENUE & COMMISSION

OCT 1-1 1960

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
RUSSELL COUNTY } SS.

I hereby certify that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING CO.

By Quincy Lee Marshall

Subscribed and sworn to before me this 6th day of October, 1960.

Clara L. Hummel
Notary Public

My Commission Expires 6/17/62