

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Seward County, Sec. 35 Twp. 33 Rge. (E) 13 (W)

Location as "NE/CNW4SW4" or footage from lines C-NE-SW

Lease Owner J. M. Huber Corporation

Lease Name Keating Well No. 1

Office Address Box 978 Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed April 29 1962

Application for plugging filed April 29 1962

Application for plugging approved April 29 1962

Plugging commenced April 29 1962

Plugging completed April 30 1962

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production -- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Fred W. Hampel

Producing formation None Depth to top Bottom Total Depth of Well 6055 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None				9 5/8	1512	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/mud to 500'. Pushed Halliburton plug w/sack hulls to 500' cemented w/30 sx. cement. Filled hole w/mud to 50'. Pushed plug w/sx. of hulls to 50' and cemented to surface w/20 sx. cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 3 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor McClellan Drilling Company, Inc.
Address Liberal, Kansas

STATE OF Kansas, COUNTY OF Seward, ss.
Floyd L. Meade (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Floyd L. Meade

Box 978 Liberal, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of July, 1962

My commission expires August 5, 1964

Lydia M. Woods

Notary Public.



COMMENCED: 4-07-62
 COMPLETED: 4-29-62
 Log 2 logs, 100' of 1 1/2" OD Spiral
 bit and 100' of 1 1/2" OD, of 32"
 5/8" tubing, and 100' of 1 1/2" V.B.
 cement with 100 sacks cement, 2' of
 and 100 sacks cement, 2' of,
 cement included.

FORMATION	FROM	TO
Sand, Shale, Shelly	0	580
Red Red	580	900
Shale and Sand	900	953
Red Red and Sand	953	1450
Red Red and Anhydrite	1450	2325
Lime and Sand	2325	3119
Lime, Shale and Shelly	3119	3258
Lime and Shale	3258	3446
Lime, Shale and Shelly	3446	3555
Lime and Shale	3555	4490
Lime	4490	4682
Lime and Shale	4682	4750
Lime	4750	4854
Lime and Shale	4854	4903
Lime	4903	5150
Lime and Shale Shelly	5150	5208
Lime	5208	5261
Lime and Shale Shelly	5261	5355
Lime	5355	5410
Lime and Shale Shelly	5410	5538
Lime and Shale	5538	5833
Lime and Shale Shelly	5833	5920
Lime	5920	6055


RECEIVED
 STATE PETROLEUM COMMISSION
 JUL 3 1962
 CONSERVATION DIVISION
 Topeka, Kansas

RTD


STATE OF KANSAS
 COUNTY OF NOWARD

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Feetings #1 well, located NE-SW of Section 35-34-31W, Noward County, Kansas.

McCLELLAN DRILLING INC.


 C. J. McClellan, Manager

Witnessed and sworn to before me a notary public this 10th day of July, 1962.


 Notary Public

I hereby certify that the above and foregoing is a true and correct copy of the log of the Feetings #1 well, located NE-SW of Section 35-34-31W, Noward County, Kansas.