


Give Attention to: Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Seward County, Sec. 35 Twp. 33S Rge. 31 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE NW
Lease Owner A. L. Abercrombie, Inc.
Lease Name Higgins Well No. 2
Office Address 801 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 19____
Application for plugging filed Nov. 1 1973
Application for plugging approved Nov. 2 1973
Plugging commenced 2-12 1974
Plugging completed 2-15 1974
Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5970 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1254	none
				5 1/2	4555	2910

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pump 20 sks. of cement @ 4200
Pump 35 sks. of cement @ 900 to 800
Put 15 sks. of cement @ 45 to 0

RECEIVED
STATE CORPORATION COMMISSION
MAR 5 1974
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service Kansas No. 511
Address Box 506 Liberal, Kansas 67901

STATE OF Kansas, COUNTY OF Sedgwick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. L. Abercrombie
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 4 day of March, 1974

My commission expires 2-10-74
Dorothy Mann
Notary Public.

HIGGINS NO 2
Panhandle Development Company, Inc.
Section 35-33s-31w
Seward County, Kansas

Casing Record:

Commenced: 12-03-61
Completed: 12-26-61

Ran 38 joints of new 8.5/8" O.D. Casing,
set at 1244.22 G.L., Cemented with 500
sacks Pozmix, 24 CC and 200 sacks HA-5.
Ran 145 joints of new 5 1/2" O.D. 14" casing,
set at 4555' H.B. Cemented with 125 sacks
salt saturated cement.

Formation:	From	To
Surface soil & clay	0	75
Sand & shale	75	510
Red Bed	510	775
Red Bed, gyp & shells	775	1465
Red Bed & shale	1465	1935
Shale & anhydrite	1935	2215
Shale & lime	2215	2520
Lime	2520	2750
Lime & shale	2750	2890
Lime	2890	3195
Lime & chalk	3195	3370
Lime	3370	3955
Lime & shale	3955	4037
Lime	4037	4265
Lime & shale	4265	4325
Lime	4325	5542
Lime & shale	5542	5792
Lime	5792	5970 RTD

RECEIVED
STATE CORPORATION COMMISSION
NOV 2 1973
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas)
) SS
County of Seward)

I Hereby affirm that the above and foregoing is a true and correct copy of the log of the Higgins No 2 well, located C-SE-NW of Section 35-33s-31w, Seward County, Kansas.

McCLIVILAN DRILLING COMPANY

by [Signature]
Manager

Subscribed and sworn to before me a notary public this 29th
day of December, 1961.

[Signature]
Notary Public

My Commission Expires:
September 26, 1965