

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-119-00151-0001
API NUMBER 8-21-53

LEASE NAME Armentrout

WELL NUMBER B # 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

SE NW Ft. from S Section Line

_____ Ft. from E Section Line

LEASE OPERATOR Berexco Inc.

SEC. 15 TWP. 33 SRGE. 30W (E) or (W)

ADDRESS 970 Fourth Financial Ctr. Wichita, Ks. 67202

COUNTY Meade

PHONE# (316) 265-3311 OPERATORS LICENSE NO. 05363

Date Well Completed 7/20/53

Character of Well Oil

Plugging Commenced 12-6-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-11-90

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City Lacy

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation LANSING Depth to Top 4556 Bottom 4560 T.O. 5840

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				13 3/8	652	0
				9 5/8	2694	0
				5 1/2	5837	3100

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
CIBP @ 5670 w/2 sks. of cement Pump 25 sks. of cement to 4400, test pump between 9 5/8 & 13 3/8 to 400 # & hold
Pump 50 sks. of cement from 1670 to 1570 Pump 40 sks. of cement from 670 to 570
Put 10 sks. of cement from 40 to 0 Cut off & cap 13 3/8 4' below ground level
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Eron C May

(Address) _____

SUBSCRIBED AND SWORN TO before me this 31st day of January, 19 91

Johanna S. Dobler
Notary Public

My Commission Expires: 10/31/94

