

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20529-0000

LEASE NAME Armentrout B

WELL NUMBER 2

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 15 TWP. 33S RGE. 30 ~~KEY~~ (W)

COUNTY Meade

Date Well Completed 11/5/81

Plugging Commenced 6/16/86

Plugging Completed 7/14/86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Cities Service Oil and Gas Corporation

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112

PHONE#(405) 949-4432 OPERATORS LICENSE NO. 5447

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District Office #1

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Marmaton Depth to Top 4564 Bottom 4568 T.D. 6220'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Marmaton	oil	4564	68	8-5/8"	1574'	0
				5-1/2"	4740'	2111

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

RTH w/5.5" CIBP to 4440' KB. Set CIBP. Dumped 2 sx cmt on top of plug. Loaded hole w/30 bbls. mud. Shot off csg at 3290'. Pulled csg to 3210'. Set 40 sx cmt plug at 3210'. Re-shot csg at 2825' and at 2043'. POOH w/csg to 1635'. Spotted 50 sx cmt plug. Spotted 10 sx plug at 42' to surf. Cut off flange. Welded on slate.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor DACO, Inc. License No. _____

Address Drawer 3010, Borger, Texas 79008

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Del G. Oliver, Engineering Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Del G. Oliver
3545 NW 58th Street

(Address) Oklahoma City, Oklahoma 73112

SUBSCRIBED AND SWORN TO before me this 22 day of July, 1986

My Commission Expires: 4-24-89

RECEIVED
STATE CORPORATION COMMISSION
Notary Public