

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Meade County, Sec. 15 Twp. 33S Rge. (E) 30 (W)

Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner United Petroleum Co. & Circle Oil Company
Lease Name Hush Well No. 1
Office Address Suite 214, Page Court, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 14, 19 71
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced December 14, 19 71
Plugging completed December 14, 19 71
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Edgar Eves of Sublette)

Name of Conservation Agent who supervised plugging of this well
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5815' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	1530'	8-5/8"	11/29/71	----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy Mud from Total Depth to 1000 Feet,
35 sax from 1000 feet to 900 feet; Mud
to 45 feet, 1/2 sax hulls and plug bridged
and 15 sax cement to base of cellar; 2 sax
in rat hole. Job completed @ 10:30 A.M.

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor HOWCO
Address Box 129, Liberal, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Clarence Michael of Sage Drilling Co. (employee of owner) or owner or operator of the above described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael
500 Bitting Bldg., Wichita, Kansas
(Address)



SUBSCRIBED AND SWORN to before me this 17th day of December, 1971

Louise K. Whitted
Louise K. Whitted - Notary Public.

My commission expires November 26, 1974.

DRILLERS LOGHUSH NO. 1

CASING RECORD:	OPERATOR:	United Petroleum Co. & Circle Oil Company	DESCRIPTION:
8-5/8" @ 1530' w/780 sax cement	CONTRACTOR:	Sage Drilling Co.	C NE SW Sec. 15-33S-30W Meade County, Kansas
TOTAL DEPTH:	COMMENCED:	November 29, 1971	ELEVATION: 2731KB
5815'	COMPLETED:	December 14, 1971	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	502	
Sand & Red Bed	502	1050	
Sand	1050	1107	
Shale	1107	1531	
Shale & Gyp	1531	1900	
Shale	1900	2462	
Shale & Lime	2462	2639	
Shale	2639	2775	
Lime & Shale	2775	3140	
Shale & Lime	3140	3347	
Lime & Shale	3347	5120	
Shale	5120	5210	
Lime & Shale	5210	5330	
Shale	5330	5396	
Lime & Shale	5396	5732	
Shale & Sand	5732	5754	
Sand & Shale	5754	5791	
Sand, Lime & Shale	5791	5815	D&A

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1971
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Clarence Michael
Clarence Michael



Subscribed and sworn to before me this 17th day of December, 1971.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.